



Errata to the  
2014 Oregon Structural Specialty Code

~~Strikethrough~~ text represents deleted language.

Underlined text represents added language.

**Errata Summary:**

- Section 1108.2.9

**Chapter 11 Accessibility**

**1108.2.9 Dining and drinking areas.** In dining and drinking areas, all interior and exterior floor areas shall be *accessible*.

**Exceptions:**

1. An *accessible route* between *accessible* levels and stories above or below is not required where permitted by Section 1104.4, Exception 1.
- ~~2. In buildings or facilities not required to provide an *accessible route* between stories, an *accessible route* to a *mezzanine* is not required, provided that the *mezzanine* contains less than 25 percent of the total area and the same services, decor and amenities are provided in the *accessible* area.~~
- 3-2. In sports facilities, tiered dining areas providing seating required to be *accessible* shall be required to have *accessible routes* serving at least 25 percent of the dining area, provided that *accessible routes* serve *accessible* seating and where each tier is provided with the same services.
- 4-3. Employee-only work areas shall comply with Sections 1103.2.3 and 1104.3.1.

**Contact:** Visit the division website to [contact a building code specialist](#).

