

OPERATION & MAINTENANCE MANUAL

DFI No.: D00152

**Facility Type: Water Quality Biofiltration
Facility**



AUGUST, 2011

INDEX

1. IDENTIFICATION..... 1

2. FACILITY CONTACT INFORMATION..... 1

3. CONSTRUCTION..... 1

4. STORM DRAIN SYSTEM AND FACILITY OVERVIEW 1

5. FACILITY HAZ MAT SPILL FEATURE(S)..... 5

6. AUXILIARY OUTLET (HIGH FLOW BYPASS)..... 5

7. MAINTENANCE REQUIREMENTS..... 5

8. WASTE MATERIAL HANDLING..... 6

APPENDIX A: Operational Plan and Profile Drawing(s)

APPENDIX B: ODOT Project Plan Sheets

1. Identification

Drainage Facility ID (DFI): **D00152**

Facility Type: Water Quality Biofiltration Swale

Construction Drawings: (V-File Number) 31V-41

Location: District: 1 (Old 2A)

Highway No.: 102

Mile Post: 88.94 (beg./end)

Description: This facility is located on the northeast corner of OR 47 (Hwy 102) and Beal Road intersection. The facility can be located by an access pullout with access gate on the northeast side of the highway, just southeast of the intersection.

2. Facility Contact Information

Contact the Engineer of Record, Region Technical Center, or Geo-Environmental's Senior Hydraulics Engineer for:

- Operational clarification
- Maintenance clarification
- Repair or restoration assistance

Engineering Contacts:

Region Technical Center Hydro Unit Manager

Or

Geo-Environmental Senior Hydraulics Engineer (503) 986-3365.

3. Construction

Engineer of Record: County Designer - Washington County
Engineering, Jim Perkins, P.E., 503-846-7900

Facility construction: 1998

Contractor: Huffman-Wright Construction Company

4. Storm Drain System and Facility Overview

A water quality swale is a flat-bottomed open channel designed to treat stormwater runoff from highway pavement areas. This type of facility is lined with grass. Treatment by trapping sedimentation occurs when stormwater runoff flows through the grass.

The swale is located on the southeast corner of US 47 (Hwy 102) and Beal Road Intersection. The swale lies with an access control area adjacent to Council Creek and is near a conservation easement. The swale can be accessed through a locked gate.

The swale treats stormwater runoff on both sides of the highway for a distance of approximately 750 feet. Stormwater runoff is conveyed by roadway ditches along both sides of the highway. The southwest corner of the intersection of US 47 and Beal Road is partially improved with curb and gutter. A series of inlets both on the north and south collect the runoff at a low (sag) point in the roadway.

A split-flow manhole located upstream of the facility (Point A of the Operational Plan, Appendix A) is used to bypass the water quality flows into the facility and convey the high flows through a separate 15-inch pipe and conveyance system that discharges into Council Creek. The high flows do not receive treatment.

The low flows are first pretreated through pollution control manhole (Point B in the Operational Plan) before being conveyed by a 12-inch storm pipe to the water quality swale. The treated stormwater leaves the water quality swale through an open channel and is ultimately discharged into Council Creek.

A. Maintenance equipment access:

Maintenance access can be obtained from US 47 (Hwy 102). The facility contains a paved access pullout (Photo 4).

B. Heavy equipment access into facility:

- Allowed (no limitations)
- Allowed (with limitations) – Facility is within a locked access control area. Access to the swale requires a key.
- Not allowed

C. Special Features:

- Amended Soils
- Porous Pavers
- Liners

☐ Underdrains



Photo 1: Looking towards the east at the WQ biofiltration swale within the Access Control Area. Council Creek is shown to the left while US47 (Hwy 102) is to the right.




Photo 2: Looking towards the southeast at the roadside drainage ditch.



Photo 3: Looking southeast at inlets located along the north side of highway.



Photo 4: Looking northwest at the access pullout and intersection of US47 (Hwy 102) and Beal Road.



Photo 5: Swale Inlet.

5. Facility Haz Mat Spill Feature(s)

The swale can not be effectively used to store a volume of liquid. The swale disperses the runoff to a nearby field with no outlet control.

6. Auxiliary Outlet (High Flow Bypass)

Auxiliary Outlets are provided if the primary outlet control structure can not safely pass the projected high flows. Broad-crested spillway weirs and over flow risers are the two most common auxiliary outlets used in stormwater treatment facility design. The auxiliary outlet feature is either a part of the facility or an additional storm drain feature/structure.

The auxiliary outlet feature for this facility is:

Designed into facility

Other, as noted –

There are no auxiliary outlet features provided for in this facility.

7. Maintenance Requirements

Routine maintenance table for non-proprietary stormwater treatment and storage/detention facilities have been incorporated into ODOT's Maintenance Guide. These tables summarize the maintenance requirements for ponds, swales, filter strips, bioslopes, and detention

tanks and vaults. Special maintenance requirements in addition to the routine requirements are noted below when applicable.

The ODOT Maintenance Guide can be viewed at the following website:

<http://www.oregon.gov/ODOT/HWY/OOM/MGuide.shtml>

Maintenance requirements for proprietary structures, such as underground water quality manholes and/or vaults with filter media are noted in Appendix C when applicable.

The following stormwater facility maintenance table (See ODOT Maintenance Guide) should be used to maintain the facility outlined in this Operation and Maintenance Manual or follow the Maintenance requirements outlined in Appendix C when proprietary structure is selected below:

- Table 1 (general maintenance)
- Table 2 (stormwater ponds)
- Table 3 (water quality biofiltration swales)
- Table 4 (water quality filter strips)
- Table 5 (water quality bioslopes)
- Table 6 (detention tank)
- Table 7 (detention vault)
- Appendix C (proprietary structure)
- Special Maintenance requirements:

Note: Special maintenance Requirements Require Concurrence from ODOT SR Hydraulics Engineer.

8. Waste Material Handling

Material removed from the facility is defined as waste by DEQ. Refer to the roadwaste section of the ODOT Maintenance Yard Environmental Management System (EMS) Policy and Procedures Manual for disposal options: <http://egov.oregon.gov/ODOT/HWY/OOM/EMS.shtml>


Contact any of the following for more detailed information about management of waste materials found on site:

ODOT Clean Water Unit	(503) 986-3008
ODOT Statewide Hazmat Coordinator	(503) 229-5129
ODOT Region Hazmat Coordinator	(503) 731-8290
ODEQ Northwest Region Office	(503) 229-5263


Appendix A

Content:


- **Operational Plan and Profile Drawing(s)**




Plan
N.T.S.



HIGH-LOW SPLIT FLOW MANHOLE DETAIL AT POINT A
N.T.S.



Section B-B
N.T.S.



Section A-A
N.T.S.

- LEGEND:**
- Photo Location / Direction
 - High-Low Split Flow Manhole
 - Pollution Control Manhole
 - Swale inlet/Flow Spreader
 - Manhole
 - Inlet
 - Storm Pipe (Facility)
 - Storm Pipe
 - Conveyance Direction
 - Pavement / Facility Flow Path
 - Gate

Sht. 1 of 1 OREGON DEPARTMENT OF TRANSPORTATION

Prepared By: Bob Knorr
 Drafted By: Jim Holeman

DFI D00152
MAINTENANCE DISTRICT 1 HWY 102
WATER QUALITY BIOFILTRATION SWALE
 NEHALEM HWY 102 MP 88.94
 WASHINGTON COUNTY

Appendix B

Content:

- **ODOT Project Plan Sheets**
 - *Cover/Title Sheet*
 - *Water Quality/Detention Plan Sheets*
 - *Other Details*


STATE OF OREGON
DEPARTMENT OF TRANSPORTATION

PLANS FOR PROPOSED PROJECT

GRADING, STRUCTURE, PAVING, SIGNING, SIGNAL, & STRIPING

**COUNCIL CR. - QUINCE ST.
(FOREST GROVE) SEC.**

**NEHALEM HIGHWAY
WASHINGTON COUNTY
OCTOBER 1998**



Overall Length Of Project - 3.33 km (2.07 Miles)

ATTENTION:
Oregon Law Requires You To Follow Rules
Adopted By The Oregon Utility Notification Center.
Those Rules Are Set Forth In OAR 952-001-0010 Through
OAR 952-001-0090. You May Obtain Copies Of The Rules From The Center.

INDEX OF SHEETS	
SHEET NO.	DESCRIPTION
1	Title Sheet
1A	Index Of Sheets Cont'd. & Standard Drawing Nos.
1B	Sheet Layout
2, 2A Thru 2A-9 Incl.	Typical Sections
2B Thru 2B-20 Incl.	Details
2C Thru 2C-9 Incl.	Traffic Control Plans
2D Thru 2D-3 Incl.	Erosion Control Details
2D Thru 2D-18 Incl.	Erosion Control Plans
2E Thru 2E-4 Incl.	Pipe Data
2F	Summary
3	Alignment & General Construction
3A	Drainage & Utilities
3B	Profile
4	Alignment & General Construction
4A, 4A-2	Drainage & Utilities
4B, 4C, 4D	Alignment & General Construction
4E	Drainage & Utilities
4F, 4G	Profile
5	Alignment & General Construction
5A	Drainage & Utilities
5B	Profile
6	Alignment & General Construction
6A, 6A-2	Drainage & Utilities
6B	Profile
7	Alignment & General Construction
7A, 7A-2	Drainage & Utilities
7B	Profile
8	Alignment & General Construction
8A, 8A-2	Drainage & Utilities
8B	Profile
9	Alignment & General Construction
9A, 9A-2	Drainage & Utilities
9B, 9C	Profiles
10	Alignment & General Construction
10A, 10A-2	Drainage & Utilities
10B, 10C	Profiles
11	Alignment & General Construction
11A, 11A-2	Drainage & Utilities
11B	Alignment & General Construction
11C	Drainage & Utilities
11D, 11E	Profiles
12	Alignment & General Construction
12A, 12A-2	Drainage & Utilities
12B	Profile


**NH-S102(4)
END OF PROJECT**
STA. "L" 4+130
(M.P. 17.88 - Hwy. No. 29)



**NH-S102(4)
BEGINNING OF PROJECT**
STA. "L" 1+000
(M.P. 88.69 - Hwy. No. 102)

- OREGON TRANSPORTATION COMMISSION
- Henry H. Hewitt CHAIRMAN
 - Susan Brody VICE CHAIRMAN
 - Steven H. Corey COMMISSIONER
 - Stuart Foster COMMISSIONER
 - John Russell COMMISSIONER
 - Grace Crunican DIRECTOR OF TRANSPORTATION

PLANS PREPARED BY:
WASHINGTON COUNTY





OREGON DEPARTMENT OF TRANSPORTATION
CONCURRENCE

Oliver Schuch 9/29/98
TECHNICAL SERVICES MANAGING ENGINEER DATE

**COUNCIL CR. - QUINCE ST.
(FOREST GROVE) SEC.
NEHALEM HIGHWAY
WASHINGTON COUNTY**

FEDERAL HIGHWAY ADMINISTRATION		PROJECT NUMBER	SHEET NO.
REGION 10	OREGON DIVISION		1




25-SEP-1998 10:20

C:\US1\p\o\ec\34\354r1.mcd

END OF CONTRACT PROJECT
STA. "L" 4+327.1
(M.P. 17.76 - Hwy. No. 29)




OUTLET BASIN



PLAN
N.T.S.

SECTION B-B
N.T.S.



SECTION A-A
N.T.S.

20 AUG 98
0222417 04364043641.dwg





COUNCIL CR.-QUINCE ST. (FOREST GROVE) SEC.			
NEHALEM HWY.			
WASHINGTON COUNTY			
FEDERAL HIGHWAY ADMINISTRATION		PROJECT NUMBER	SHEET NO.
REGION 10	OREGON DIVISION	NH-S102 (4)	2B-6



CONTROL MANHOLE

Sta.	Sheet/Note	Top Weir Elev.	Flow Line Pipe Elevation		
			Inlet	High Flow	Low Flow
1+457	4A-2 Note 6	49.280	49.120	49.100	49.100
1+848	6A-2 Note 7	49.400	49.246	49.220	49.220
2+155	7A-2 Note 5	49.250	49.080	49.070	49.070
2+566	8A-2 Note 6	48.980	48.817	48.800	48.800
2+805	9A-2 Note 6	50.350	50.175	50.170	50.170
3+385	11A-2 Note 3	48.825	48.665	48.645	48.645



SECTION A-A

N.T.S.



COUNCIL CR.-QUINCE ST. (FOREST GROVE) SEC.			
NEHALEM HWY.			
WASHINGTON COUNTY			
FEDERAL HIGHWAY ADMINISTRATION	PROJECT NUMBER	SHEET NO.	
REGION 10	OREGON DIVISION	NH-S102 (4)	2B-8

20 AUG 98


0122410043660436412



DETAILS


WATER QUALITY MANHOLE

"All Dimensions Are In mm Unless Otherwise Noted"




SECTION A-A

(For Details Not Shown, See USA Standard Manhole Drawing 010-ST)



DETAIL "A"



PLAN

NOTES:

1. Hardware, Fasteners And Anchors To Be Stainless Steel; Use 3 mm Stainless Steel Cable
2. See Pipe Data Sheet And Plan Sheets For Pipe Size(s).
3. See Pipe Data Sheet And Plan Sheets For Manhole Size(s).
4. See Pipe Data Sheet And Plan Sheets For Sump Depth.
5. Manhole And Base Per Manhole Standard Drawings.
6. Hardware, Fasteners, Anchors, Fittings, Appurtenances, Labor And Equipment Is Incidental To Water Quality Manhole Item.



COUNCIL CR.-QUINCE ST. (FOREST GROVE) SEC.			
NEHALEM HWY.			
WASHINGTON COUNTY			
FEDERAL HIGHWAY ADMINISTRATION	PROJECT NUMBER	SHEET NO.	
REGION 10	OREGON DIVISION	NH-S102 (4)	2B-9




20 AUG 98

0224170-0436-0436-02




SWALE NO. 1 DETAILS

(For Location, See Sht. 4A-2, Note 8)



① Const. Water Quality Swale
Earthwork Included In
Mainline Roadwork.
Selected Topsoil - 45 m³



STA. "WQS 1" 1+462 TO STA. "WQS 1" 1+512



ROADWAY PLANS & DETAILS		COUNCIL CR.-QUINCE ST. (FOREST GROVE) SEC.	
	Richard B. Raetz Design Team Leader	NEHALEM HWY. WASHINGTON COUNTY	
	Richard B. Raetz Designer	FEDERAL HIGHWAY ADMINISTRATION	PROJECT NUMBER
	Arne E. Autlo Drafter	REGION 10	OREGON DIVISION
			SHEET NO.
			2B-10


20 AUG 99

02224104364043641.d12



DRAINAGE & UTILITIES

Sec. 30, T. 1N., R. 3W., W.M.



21 AUG 98

0224100436404364.dwg

NOTE:
1. All Dimensions Are Shown In Meters (m)
Unless Otherwise Noted.



COUNCIL CR.-QUINCE ST. (FOREST GROVE) SEC.			
NEHALEM HWY.			
WASHINGTON COUNTY			
FEDERAL HIGHWAY ADMINISTRATION		PROJECT NUMBER	SHEET NO.
REGION 10	OREGON DIVISION	NH-S102 (4)	4A



- ① Sta. 1+491.3, 13.765 m Rt.
Const. Type "D" Mod. Inlet
Inst. 300 mm Sew. Pipe - 5m
Tr. Exc. - 7 m³
(For Details, See Sht. 2B-7)
- ② Sta. 1+486.3, 13.765 m Rt.
Const. Type "D" Mod. Inlet
Inst. 300 mm Sew. Pipe - 29m
Tr. Exc. - 41 m³
(For Details, See Sht. 2B-7)
- ③ Sta. 1+457, 13.765 m Rt.
Const. Type "D" Mod. Inlet
Inst. 300 mm Sew. Pipe - 28m
Tr. Exc. - 39 m³
(For Details, See Sht. 2B-7)
- ④ Sta. 1+462, 13.765 m Lt.
Const. Type "D" Mod. Inlet
Inst. 300mm Sew. Pipe - 5 m
Tr. Exc. - 7 m³
(For Details, See Sht. 2B-7)
- ⑤ Sta. 1+457, 13.765 m Lt.
Const. Type "D" Mod. Inlet
Inst. 375 mm Sew. Pipe - 4 m
Tr. Exc. - 6 m³
(For Details, See Sht. 2B-7)
- ⑥ Sta. 1+457, 17 m Lt.
Const. Type "B-P" Control Manhole
Inst. 375 mm Sew. Pipe - 13 m
Inst. 300 mm Sew. Pipe - 4 m
Tr. Exc. - 26 m³
(For Details, See Sht. 2B-8)
(See Drg. No. RD327)
- ⑦ Sta. 1+457, 21 m Lt.
Const. Water Quality Manhole
Inst. 300 mm Sew. Pipe - 6 m
Const. Outlet Basin
Const. Loose Riprap (Class 50) - 4 m³
Outlet To Swale
Tr. Exc. - 8 m³
(For Details, See Sht. 2B-6 & 2B-9)

- ⑧ Const. Water Quality Swale No. 1
(For Details, See Sht. 2B-10)
- ⑨ Sta. 1+442, 21 m Rt. To 20 m Lt.
Inst. 900 mm Culv. Pipe - 41 m
Const. Outlet Basin
Const. Loose Riprap (Class 100) - 9 m³
Tr. Exc. - 177 m³
(For Details, See Sht. 2B-6)
- ⑩ Sta. "B" 0+455, 15m Lt. To 13 m Rt.
Inst. 600 mm Culv. Pipe - 28 m
Const. Outlet Basin
Const. Loose Riprap (Class 100) - 6 m³
Tr. Exc. - 40 m³
(For Details, See Sht. 2B-6)
- ⑪ Sta. 1+365, 22 m Rt. To STA 1+510, 74 m Lt.
Const. USA Std. Manhole - 3
Inst. 200 mm San. Sew. Pipe - 208 m
Connect To Extg. Manhole
Tr. Exc. - 150 m³
(See USA Std. Drg. No. 010-ST)
(For Profile, See Sht. 15)
- ⑫ Sta. 1+449, 13.4 m Lt.
Inst. 300 mm Culv. Pipe - 10 m
Tr. Exc. - 7 m³
- ⑬ Const. Aggregate Ditch Lining- 120 m²

22 AUG 98

D:\224\FD\043640\364.rtl

10-F-008 SHT. 4A



COUNCIL CR.-QUINCE ST. (FOREST GROVE) SEC.			
NEHALEM HWY.			
WASHINGTON COUNTY			
FEDERAL HIGHWAY ADMINISTRATION		PROJECT NUMBER	SHEET NO.
REGION 10	OREGON DIVISION	NH-S102 (4)	4A-2


ALIGNMENT & GENERAL CONSTRUCTION

31V-41



Sec. 30, 31, T. 1N., R. 3W., W.M.

- ① Const. Wash. Co. Type "CS-300" Curb and Gutter (For Details, See Sht. 2B-3)
- ①A Const. Curb Ending (For Details, See Sht. 2B-3)
- ② Const. P.C. Conc. Walk
- ③ Cold Plane Pvmt. Removal - 100 m²
- ④ Const. Walk Ending Ramp (For Details, See Sht. 2B-2)
- ⑤ Const. Appr. - 2
- ⑥ Remove Guardrail
- ⑦ Const. Porous Conc. Pvmt. - 200 m²



21 AUG 98 01224100436404364.dwg

COUNCIL CR.-QUINCE ST. (FOREST GROVE) SEC.
NEHALEM HWY.
WASHINGTON COUNTY


FEDERAL HIGHWAY ADMINISTRATION		PROJECT NUMBER	SHEET NO.
REGION 10	OREGON DIVISION	NH-S102 (4)	4B



ALIGNMENT & GENERAL CONSTRUCTION

Sec. 30, T. 1, R. 3, W.M.

- ① Const. Wetland Mitigation
See Sht. 4, Note 8
- ② Sta. "B" 0+580 Lt.
Const. Appr.
- ③ Const. Fence
See Sht. 4, Note 11



Remove Old Roadway, Shown Thus:

NOTE:
1. All Dimensions Are Shown In Meters (m)
Unless Otherwise Noted.



COUNCIL CR.-QUINCE ST. (FOREST GROVE) SEC.
NEHALEM HWY.
WASHINGTON COUNTY


FEDERAL HIGHWAY ADMINISTRATION		PROJECT NUMBER	SHEET NO.
REGION 10	OREGON DIVISION	NH-S102 (4)	4D

22 AUG 98

α-224ff0436404364.p12

DRAINAGE & UTILITIES

Sec. 30, T. 1, R. 3, W.M.



- ① See Sht. 4A-2, Note 11.
- ② Sta. "B" 0+580 Lt.
Inst. 300mm Culv. Pipe - 14m
Tr. Exc. - 6.3m

22 AUG 98



0:22:41 (V0436A0436.dwg)

NOTE:
1. All Dimensions Are Shown In Meters (m)
Unless Otherwise Noted.



COUNCIL CR.-QUINCE ST. (FOREST GROVE) SEC.
NEHALEM HWY.
WASHINGTON COUNTY

FEDERAL HIGHWAY ADMINISTRATION		PROJECT NUMBER	SHEET NO. 4E
REGION 10	OREGON DIVISION	NH-S102 (4)	



22 AUG 98

0122417004364043641.D1



COUNCIL CR.-QUINCE ST. (FOREST GROVE) SEC.			
NEHALEM HWY.			
WASHINGTON COUNTY			
FEDERAL HIGHWAY ADMINISTRATION	PROJECT NUMBER	SHEET NO.	
REGION 10	OREGON DIVISION	NH-S102 (4)	4F

1+300




1+400

1+500



PRECAST MANHOLE TYPE A-P



NOTES:
 For Cast-in-Place Manhole see Drg. No. RD324.
 For Cover and Frame details see Drg. No. RD324.
 300 mm min. wall is required between pipes in manhole.



All dimensions are in mm unless otherwise noted.

SHALLOW PRECAST MANHOLE TYPE B-P

NOTE: See Manhole type A-P for details not shown.



ALTERNATE JOINT

MINIMUM DEPTH OF MANHOLE TYPE A-P







ØD(mm)	H(mm)
200	1675
250	1750
300	1825
375	1900
450	1975
525	2050
600	2125

ØD is inside diameter of the largest pipe entering or leaving base.


NOTE: When depth is less than minimum for manhole type A-P, use shallow manhole type B or type B-P.

NOTE: Shape bottom of manhole as shown on "Plan of Base" and Section A-A for "Base, Risers & Cone"

NOTE: When H=1525 mm or less make hole for frame in center of cover slab. When H=1065 mm or less omit steps.




NOTE: The risers, cones and cover slabs shall meet the requirements of the current AASHTO Standard Specification M199M



(Steps may be substituted for ladder)

See Current Qualified Products List (QPL) For Acceptable Alternate Manhole Steps



DETAIL OF STEEL LADDER

* See Steps

Hook may be eliminated, provided steps will withstand a "pull" force of 450 kg without loosening.

LEGEND

- Cast-in-Place concrete
- Precast concrete
- 1:2 cement mortar
- Sewer pipe
- W 100 mm min. (For tolerance see AASHTO M199M)

NOTE: All material and workmanship shall be in accordance with the current State of Oregon Standard Specifications for Highway Construction.

OREGON DEPARTMENT OF TRANSPORTATION STANDARD

MANHOLES

JANUARY 1996

REVISIONS		APPROVED
DATE	DESCRIPTION	
8-96	REVISED REINFORCEMENT	<i>San Johnston</i> STANDARDS ENGINEER
4-97	REVISED STEPS DETAIL	

DRG. NO. RD327

n\7360a\rd327.met 4-17-97

RD327