

# OPERATION & MAINTENANCE MANUAL

**DFI No.: D00155**

**Facility Type: Water Quality Biofiltration  
Facility**



**AUGUST, 2011**

**INDEX**

**1. IDENTIFICATION..... 1**

**2. FACILITY CONTACT INFORMATION..... 1**

**3. CONSTRUCTION..... 1**

**4. STORM DRAIN SYSTEM AND FACILITY OVERVIEW ..... 1**

**5. FACILITY HAZ MAT SPILL FEATURE(S)..... 6**

**6. AUXILIARY OUTLET (HIGH FLOW BYPASS)..... 6**

**7. MAINTENANCE REQUIREMENTS..... 6**

**8. WASTE MATERIAL HANDLING..... 7**

**APPENDIX A: Operational Plan and Profile Drawing(s)**

**APPENDIX B: ODOT Project Plan Sheets**

## 1. Identification

Drainage Facility ID (DFI): **D00155**  
Facility Type: Water Quality Biofiltration Swale  
Construction Drawings: (V-File Number) 31V-41  
Location: District: 1 (Old 2A)  
Highway No.: 102  
Mile Post: 89.60 (beg./end)  
Description: This facility is located on the north side of OR 47 (Hwy 102) approximately 1,700 feet northwest of Porter Road. The facility can be located by an access pullout with access gate on the north side of the highway.

## 2. Facility Contact Information

Contact the Engineer of Record, Region Technical Center, or Geo-Environmental's Senior Hydraulics Engineer for:

- Operational clarification
- Maintenance clarification
- Repair or restoration assistance

### Engineering Contacts:

Region Technical Center Hydro Unit Manager

Or

Geo-Environmental Senior Hydraulics Engineer (503) 986-3365.

## 3. Construction

Engineer of Record: County Designer - Washington County  
Engineering, Jim Perkins, P.E., 503-846-7900

Facility construction: 1998  
Contractor: Huffman-Wright Construction Company

#### 4. Storm Drain System and Facility Overview

A water quality swale is a flat-bottomed open channel designed to treat stormwater runoff from highway pavement areas. This type of facility is lined with grass. Treatment by trapping sedimentation occurs when stormwater runoff flows through the grass.

The swale is located on the north side of US 47 (Hwy 102) approximately 1,700 feet north of Porter Road. The swale lies with an access control area adjacent to Council Creek and is near a conservation easement. The swale can be accessed through a locked gate.

The swale treats stormwater runoff on both sides of the highway for a distance of approximately 900 feet. Stormwater runoff is conveyed by a roadway ditch on the north side of US 47 (Hwy 102) and a curb along the south side. A series of inlets both on the north and south collect the runoff at a low (sag) point in the roadway.

A split-flow manhole located upstream of the facility (Point A of the Operational Plan, Appendix A) is used to bypass the water quality flows into the facility and convey the high flows through a separate 18-inch pipe and conveyance system that discharges into Council Creek. The high flows do not receive treatment.

The low flows are first pretreated through a pollution control manhole (Point B in the Operational Plan) before being conveyed by a 12-inch storm pipe to the water quality swale. The treated stormwater leaves the water quality swale through an open channel and is ultimately discharged into Council Creek.

A. Maintenance equipment access:

Maintenance access can be obtained from US 47 (Hwy 102). The facility contains a gravel access pullout (Photo 6).

B. Heavy equipment access into facility:

- Allowed (no limitations)
- Allowed (with limitations) – Facility is within a locked access control area. Access to the swale requires a key.
- Not allowed

C. Special Features:

- Amended Soils
- Porous Pavers
- Liners
- Underdrains




Photo 1: WQ biofiltration swale within Access Control Area. Tree line represents where Council Creek lies. Manhole in the foreground is the flow control structure.



Photo 2: Inlet to WQ swale. Pipe is a 12-inch concrete culvert.



Photo 3: Outlet to WQ Swale discharge into Council Creek. Photograph is looking northeast.



Photo 4: WQ Swale inlets just northwest of access pullout. Photograph is looking to the northwest.



Photo 5: Access gate to WQ biofiltration swale.



Photo 6: High-low split-flow manhole, looking northwest.



Photo 7: Water Quality manhole located within the Access Control Area.

## 5. Facility Haz Mat Spill Feature(s)

The swale can not be effectively used to store a volume of liquid. The swale disperses the runoff to a nearby field with no outlet control.

## 6. Auxiliary Outlet (High Flow Bypass)

Auxiliary Outlets are provided if the primary outlet control structure can not safely pass the projected high flows. Broad-crested spillway weirs and over flow risers are the two most common auxiliary outlets used in stormwater treatment facility design. The auxiliary outlet feature is either a part of the facility or an additional storm drain feature/structure.

The auxiliary outlet feature for this facility is:

Designed into facility

Other, as noted –

There are no auxiliary outlet features provided for in this facility.

## 7. Maintenance Requirements

Routine maintenance table for non-proprietary stormwater treatment and storage/detention facilities have been incorporated into ODOT's



Maintenance Guide. These tables summarize the maintenance requirements for ponds, swales, filter strips, bioslopes, and detention tanks and vaults. Special maintenance requirements in addition to the routine requirements are noted below when applicable.

The ODOT Maintenance Guide can be viewed at the following website:

<http://www.oregon.gov/ODOT/HWY/OOM/MGuide.shtml>

Maintenance requirements for proprietary structures, such as underground water quality manholes and/or vaults with filter media are noted in Appendix C when applicable.

The following stormwater facility maintenance table (See ODOT Maintenance Guide) should be used to maintain the facility outlined in this Operation and Maintenance Manual or follow the Maintenance requirements outlined in Appendix C when proprietary structure is selected below:

- Table 1 (general maintenance)
- Table 2 (stormwater ponds)
- Table 3 (water quality biofiltration swales)
- Table 4 (water quality filter strips)
- Table 5 (water quality bioslopes)
- Table 6 (detention tank)
- Table 7 (detention vault)
- Appendix C (proprietary structure)
- Special Maintenance requirements:

Note: Special maintenance Requirements Require Concurrence from ODOT SR Hydraulics Engineer.

## 8. Waste Material Handling

Material removed from the facility is defined as waste by DEQ. Refer to the roadwaste section of the ODOT Maintenance Yard Environmental Management System (EMS) Policy and Procedures Manual for disposal options: <http://egov.oregon.gov/ODOT/HWY/OOM/EMS.shtml>


Contact any of the following for more detailed information about management of waste materials found on site:

|                                   |                |
|-----------------------------------|----------------|
| ODOT Clean Water Unit             | (503) 986-3008 |
| ODOT Statewide Hazmat Coordinator | (503) 229-5129 |
| ODOT Region Hazmat Coordinator    | (503) 731-8290 |
| ODEQ Northwest Region Office      | (503) 229-5263 |


# Appendix A

## Content:


- **Operational Plan and Profile Drawing(s)**




**PLAN**  
N.T.S.



**HIGH-LOW SPLIT FLOW MANHOLE DETAIL AT POINT A**  
N.T.S.



**Section B-B**  
N.T.S.



**Section A-A**  
N.T.S.

**LEGEND:**

- Photo Location / Direction
- High-Low Split Flow Manhole
- Pollution Control Manhole
- Swale inlet/Flow Spreader
- Riprap Basin
- Manhole
- Inlet
- Storm Pipe (Facility)
- Storm Pipe
- Conveyance Direction
- Pavement / Facility Flow Path
- Gate

Sht. 1 of 1

OREGON DEPARTMENT OF TRANSPORTATION

Prepared By:  
Bob Knorr

Drafted By:  
Jim Holeman

**DFI D00155**  
**MAINTENANCE DISTRICT 1 HWY 102**  
**WATER QUALITY BIOFILTRATION SWALE**  
NEHALEM HWY 102 MP 89.60  
WASHINGTON COUNTY

# Appendix B

## Content:

- **ODOT Project Plan Sheets**
  - *Cover/Title Sheet*
  - *Water Quality/Detention Plan Sheets*
  - *Other Details*


STATE OF OREGON  
DEPARTMENT OF TRANSPORTATION

PLANS FOR PROPOSED PROJECT

GRADING, STRUCTURE, PAVING, SIGNING, SIGNAL, & STRIPING

**COUNCIL CR. - QUINCE ST.  
(FOREST GROVE) SEC.**

**NEHALEM HIGHWAY  
WASHINGTON COUNTY  
OCTOBER 1998**



Overall Length Of Project - 3.33 km (2.07 Miles)

**ATTENTION:**  
Oregon Law Requires You To Follow Rules  
Adopted By The Oregon Utility Notification Center.  
Those Rules Are Set Forth In OAR 952-001-0010 Through  
OAR 952-001-0090. You May Obtain Copies Of The Rules From The Center.

| INDEX OF SHEETS       |   |
|-----------------------|---|
| SHEET NO.             | DESCRIPTION                                     |
| 1                     | Title Sheet                                     |
| 1A                    | Index Of Sheets Cont'd. & Standard Drawing Nos. |
| 1B                    | Sheet Layout                                    |
| 2, 2A Thru 2A-9 Incl. | Typical Sections                                |
| 2B Thru 2B-20 Incl.   | Details   |
| 2C Thru 2C-9 Incl.    | Traffic Control Plans                           |
| 2D Thru 2D-3 Incl.    | Erosion Control Details                         |
| 2D Thru 2D-18 Incl.   | Erosion Control Plans                           |
| 2E Thru 2E-4 Incl.    | Pipe Data                                       |
| 2F                    | Summary   |
| 3                     | Alignment & General Construction                |
| 3A                    | Drainage & Utilities                            |
| 3B                    | Profile   |
| 4                     | Alignment & General Construction                |
| 4A, 4A-2              | Drainage & Utilities                            |
| 4B, 4C, 4D            | Alignment & General Construction                |
| 4E                    | Drainage & Utilities                            |
| 4F, 4G                | Profile   |
| 5                     | Alignment & General Construction                |
| 5A                    | Drainage & Utilities                            |
| 5B                    | Profile   |
| 6                     | Alignment & General Construction                |
| 6A, 6A-2              | Drainage & Utilities                            |
| 6B                    | Profile   |
| 7                     | Alignment & General Construction                |
| 7A, 7A-2              | Drainage & Utilities                            |
| 7B                    | Profile   |
| 8                     | Alignment & General Construction                |
| 8A, 8A-2              | Drainage & Utilities                            |
| 8B                    | Profile   |
| 9                     | Alignment & General Construction                |
| 9A, 9A-2              | Drainage & Utilities                            |
| 9B, 9C                | Profiles  |
| 10                    | Alignment & General Construction                |
| 10A, 10A-2            | Drainage & Utilities                            |
| 10B, 10C              | Profiles  |
| 11                    | Alignment & General Construction                |
| 11A, 11A-2            | Drainage & Utilities                            |
| 11B                   | Alignment & General Construction                |
| 11C                   | Drainage & Utilities                            |
| 11D, 11E              | Profiles  |
| 12                    | Alignment & General Construction                |
| 12A, 12A-2            | Drainage & Utilities                            |
| 12B                   | Profile   |


**NH-S102(4)  
END OF PROJECT  
STA. "L" 4+130  
(M.P. 17.88 - Hwy. No. 29)**



**NH-S102(4)  
BEGINNING OF PROJECT  
STA. "L" 1+000  
(M.P. 88.69 - Hwy. No. 102)**

- OREGON TRANSPORTATION COMMISSION
- Henry H. Hewitt CHAIRMAN
  - Susan Brody VICE CHAIRMAN
  - Steven H. Corey COMMISSIONER
  - Stuart Foster COMMISSIONER
  - John Russell COMMISSIONER
  - Grace Crunican DIRECTOR OF TRANSPORTATION

PLANS PREPARED BY:  
**WASHINGTON COUNTY**





OREGON DEPARTMENT OF TRANSPORTATION  
CONCURRENCE

*Oliver Schuch* 9/29/98  
TECHNICAL SERVICES MANAGING ENGINEER DATE

**COUNCIL CR. - QUINCE ST.  
(FOREST GROVE) SEC.  
NEHALEM HIGHWAY  
WASHINGTON COUNTY**

|                                |                 |           |
|--------------------------------|-----------------|-----------|
| FEDERAL HIGHWAY ADMINISTRATION | PROJECT NUMBER  | SHEET NO. |
| REGION 10                      | OREGON DIVISION | 1         |




25-SEP-1998 10:20

C:\US1\p\o\ec\34\354r1.mcd

**END OF CONTRACT PROJECT**  
STA. "L" 4+327.1  
(M.P. 17.76 - Hwy. No. 29)




# OUTLET BASIN



PLAN  
N.T.S.

SECTION B-B  
N.T.S.



SECTION A-A  
N.T.S.

20 AUG 98  
022417 04364043641.d12





|   |                 |                |           |
|---|-----------------|----------------|-----------|
| COUNCIL CR.-QUINCE ST. (FOREST GROVE) SEC.<br>NEHALEM HWY.<br>WASHINGTON COUNTY |                 |                |           |
| FEDERAL HIGHWAY ADMINISTRATION  |                 | PROJECT NUMBER | SHEET NO. |
| REGION 10   | OREGON DIVISION | NH-S102 (4)    | 2B-6      |



# CONTROL MANHOLE

| Sta.  | Sheet/Note   | Top Weir Elev. | Flow Line Pipe Elevation |           |          |
|-------|--------------|----------------|--------------------------|-----------|----------|
|       |              |                | Inlet                    | High Flow | Low Flow |
| 1+457 | 4A-2 Note 6  | 49.280         | 49.120                   | 49.100    | 49.100   |
| 1+848 | 6A-2 Note 7  | 49.400         | 49.246                   | 49.220    | 49.220   |
| 2+155 | 7A-2 Note 5  | 49.250         | 49.080                   | 49.070    | 49.070   |
| 2+566 | 8A-2 Note 6  | 48.980         | 48.817                   | 48.800    | 48.800   |
| 2+805 | 9A-2 Note 6  | 50.350         | 50.175                   | 50.170    | 50.170   |
| 3+385 | 11A-2 Note 3 | 48.825         | 48.665                   | 48.645    | 48.645   |
|       |              |                |                          |           |          |
|       |              |                |                          |           |          |



20 AUG 98

0122410043660436412




|  |                 |             |      |
|--|-----------------|-------------|------|
| COUNCIL CR.-QUINCE ST. (FOREST GROVE) SEC. |                 |             |      |
| NEHALEM HWY.                               |                 |             |      |
| WASHINGTON COUNTY                          |                 |             |      |
| FEDERAL HIGHWAY ADMINISTRATION             | PROJECT NUMBER  | SHEET NO.   |      |
| REGION 10                                  | OREGON DIVISION | NH-S102 (4) | 2B-8 |



# DETAILS


## WATER QUALITY MANHOLE

"All Dimensions Are In mm Unless Otherwise Noted"



SECTION A-A

(For Details Not Shown, See USA Standard Manhole Drawing 010-ST)




DETAIL "A"

Locate Pipes, Etc. So That No Portion Of Them Are Within Min. Clear Work Area

M.H. Dia. To Be Determined By Size Of Outlet Pipe And Min. Clear Work Area Requirements:  
 100 mm - 525 mm Pipe = 1500 mm Dia. MH Min.  
 600 mm + = Pipe MH Dia. To Be Designed  
 Max. Sump Depth 1500 mm

NOTES:

1. Hardware, Fasteners And Anchors To Be Stainless Steel; Use 3 mm Stainless Steel Cable
2. See Pipe Data Sheet And Plan Sheets For Pipe Size(s).
3. See Pipe Data Sheet And Plan Sheets For Manhole Size(s).
4. See Pipe Data Sheet And Plan Sheets For Sump Depth.
5. Manhole And Base Per Manhole Standard Drawings.
6. Hardware, Fasteners, Anchors, Fittings, Appurtenances, Labor And Equipment Is Incidental To Water Quality Manhole Item.



PLAN



|  |                 |             |      |
|--|-----------------|-------------|------|
| COUNCIL CR.-QUINCE ST. (FOREST GROVE) SEC. |                 |             |      |
| NEHALEM HWY.                               |                 |             |      |
| WASHINGTON COUNTY                          |                 |             |      |
| FEDERAL HIGHWAY ADMINISTRATION             | PROJECT NUMBER  | SHEET NO.   |      |
| REGION 10                                  | OREGON DIVISION | NH-S102 (4) | 2B-9 |

20 AUG 98




02241700436404364.d12






# SWALE NO. 4 DETAILS

(For Location, See Sht. 8A-2, Note 9)



① Const. Water Quality Swale  
 Swale Exc. - 263 m<sup>3</sup>  
 Selected Topsoil - 74 m<sup>3</sup>



**COUNCIL CR.-QUINCE ST. (FOREST GROVE) SEC.  
 NEHALEM HWY.  
 WASHINGTON COUNTY**


|                                |                 |                   |
|--------------------------------|-----------------|-------------------|
| FEDERAL HIGHWAY ADMINISTRATION | PROJECT NUMBER  | SHEET NO.         |
| REGION 10                      | OREGON DIVISION | NH-S102 (4) 2B-13 |

20 AUG 98  
 022417 00436404364# 213

# D R A I N A G E & U T I L I T I E S

Sec. 31, 32, T. 1N, R. 3W, W.M.

31V-41



**NOTE:**  
1. All Dimensions Are Shown In Meters (m)  
Unless Otherwise Noted.



|   |                    |                |              |
|---|--------------------|----------------|--------------|
| <b>COUNCIL CR.-QUINCE ST. (FOREST GROVE) SEC.</b> |                    |                |              |
| NEHALEM HWY.                                      |                    |                |              |
| WASHINGTON COUNTY                                 |                    |                |              |
| FEDERAL HIGHWAY<br>ADMINISTRATION                 |                    | PROJECT NUMBER | SHEET<br>NO. |
| REGION<br>10                                      | OREGON<br>DIVISION | NH-5102 (4)    | 8A           |

22 AUG 98

022241 043640436# 213



- ① *Bridge No. 18618*  
*Sta. 2+574*  
*Const. 2 - 2700 x 2100 mm R.C.B.C. - 36 m*  
*Skew 66°30'*  
*Const. Wingwall & Aprons*  
*Const. Loose Riprap (Class 100) - 25 m<sup>3</sup>*  
*Stone Embankment - 76 m<sup>3</sup>*  
*Granular Str. Backfill - 155 m<sup>3</sup>*  
*Str. Exc. - 802 m<sup>3</sup>*  
*Subgrade Geotextile - 507 m<sup>2</sup>*  
*(For Drg. Nos., See Sht. 1A)*
  
- ② *Sta. 2+555, 11.365 m Rt.*  
*Const. Type "D" Mod. Inlet*  
*Inst. 300 mm Sew. Pipe - 5m*  
*Tr. Exc. - 4 m<sup>3</sup>*  
*(For Details, See Sht. 2B-7)*
  
- ③ *Sta. 2+550, 11.365 m Rt.*  
*Const. Type "D" Mod. Inlet*  
*Inst. 300 mm Sew. Pipe - 23 m*  
*Tr. Exc. - 21 m<sup>3</sup>*  
*(For Details, See Sht. 2B-7)*
  
- ④ *Sta. 2+545, 11.365 m Lt.*  
*Const. Type "D" Mod. Inlet*  
*Inst. 300mm Sew. Pipe - 5 m*  
*Tr. Exc. - 4 m<sup>3</sup>*  
*(For Details, See Sht. 2B-7)*
  
- ⑤ *Sta. 2+550, 11.365 m Lt.*  
*Const. Type "D" Mod. Inlet*  
*Inst. 450 mm Sew. Pipe - 16 m*  
*Tr. Exc. - 16 m<sup>3</sup>*  
*(For Details, See Sht. 2B-7)*
  
- ⑥ *Sta. 2+566, 13 m Lt.*  
*Const. Type "B-P" Control Manhole*  
*Inst. 450 mm Sew. Pipe - 12 m*  
*Inst. 300 mm Sew. Pipe - 4 m*  
*Tr. Exc. - 15 m<sup>3</sup>*  
*(For Details, See Sht. 2B-8)*
  
- ⑦ *Sta. 2+568, 17 m Lt.*  
*Const. Water Quality Manhole*  
*Inst. 300 mm Sew. Pipe - 5 m*  
*Const. Outlet Basin*  
*Const. Loose Riprap (Class 50) - 4 m<sup>3</sup>*  
*Tr. Exc. - 4 m<sup>3</sup>*  
*(For Details, See Sht. 2B-6 & 2B-9)*
  
- ⑧ *Sta. 2+562, 11.06 m Lt.*  
*Inst. 300mm Culv. Pipe - 10 m*  
*Tr. Exc. - 7 m<sup>3</sup>*
  
- ⑨ *Const. Water Quality Swale No. 4*  
*(For Details, See Sht. 2B-13)*

22 AUG 98


01224\F\00436\04364.dwg

To Face Sht. 8A



**COUNCIL CR.-QUINCE ST. (FOREST GROVE) SEC.**  
 NEHALEM HWY.  
 WASHINGTON COUNTY

|                                |                 |                |           |
|--------------------------------|-----------------|----------------|-----------|
| FEDERAL HIGHWAY ADMINISTRATION |                 | PROJECT NUMBER | SHEET NO. |
| REGION 10                      | OREGON DIVISION | NH-S102 (4)    | 8A-2      |



22 AUG 98

122410036404364 d1



**COUNCIL CR.-QUINCE ST. (FOREST GROVE) SEC.**  
 NEHALEM HWY.  
 WASHINGTON COUNTY

|                                |                 |                |           |
|--------------------------------|-----------------|----------------|-----------|
| FEDERAL HIGHWAY ADMINISTRATION |                 | PROJECT NUMBER | SHEET NO. |
| REGION 10                      | OREGON DIVISION | NH-S102 (4)    | 8B        |

Exc. 6971

Emb. In Place 2969

2+400




2+500

2+600



**PRECAST MANHOLE TYPE A-P**

**NOTES:**  
 For Cast-in-Place Manhole see Drg. No. RD324.  
 For Cover and Frame details see Drg. No. RD324.  
 300 mm min. wall is required between pipes in manhole.



**ALTERNATE JOINT**

MINIMUM DEPTH OF MANHOLE TYPE A-P



| ØD(mm) | H(mm) |
|--------|-------|
| 200    | 1675  |
| 250    | 1750  |
| 300    | 1825  |
| 375    | 1900  |
| 450    | 1975  |
| 525    | 2050  |
| 600    | 2125  |

ØD is inside diameter of the largest pipe entering or leaving base.

NOTE: When depth is less than minimum for manhole type A-P, use shallow manhole type B or type B-P.



**SHALLOW PRECAST MANHOLE TYPE B-P**

NOTE: See Manhole type A-P for details not shown.




NOTE: When H=1525 mm or less make hole for frame in center of cover slab. When H=1065 mm or less omit steps.



4-17-97 n17360a/rd327.met



NOTE: Set pipes for catch basin connections in base, to grade and directions furnished by the engineer.




NOTE: Use Section B-B-3 when length of risers become less than minimum shown.





See Current Qualified Products List (QPL) For Acceptable Alternate Manhole Steps

Hook may be eliminated, provided steps will withstand a "pull" force of 450 kg without loosening.



NOTE: Use Section D-D when length of riser becomes less than minimum shown.



NOTE: The risers, cones and cover slabs shall meet the requirements of the current AASHTO Standard Specification M199M

**LEGEND**

|                        |  |
|------------------------|--|
| Cast-in-Place concrete |  |
| Precast concrete       |  |
| 1:2 cement mortar      |  |
| Sewer pipe             |  |

W 100 mm min. (For tolerance see AASHTO M199M)

NOTE: All material and workmanship shall be in accordance with the current State of Oregon Standard Specifications for Highway Construction.

OREGON DEPARTMENT OF TRANSPORTATION STANDARD

**MANHOLES**

JANUARY 1996

| DATE | REVISIONS DESCRIPTION | APPROVED |
|------|-----------------------|----------|
| 8-96 | REVISED REINFORCEMENT |          |
| 4-97 | REVISED STEPS DETAIL  |          |
|      |                       |          |

STANDARDS ENGINEER

DRG. NO. RD327

RD327