

OPERATION & MAINTENANCE MANUAL

DFI No. : D00681

Facility Type: Extended Detention Pond

February, 2019



Figure 1: DFI NO. D00681, looking north from the Sunrise Expressway Highway

INDEX

- 1. IDENTIFICATION 1**
- 2. FACILITY CONTACT INFORMATION 1**
- 3. CONSTRUCTION 1**
- 4. STORM DRAIN SYSTEM AND FACILITY OVERVIEW 1**
- 5. FACILITY HAZ MAT SPILL FEATURE(S) 4**
- 6. AUXILIARY OUTLET (HIGH FLOW BYPASS) 4**
- 7. MAINTENANCE REQUIREMENTS 5**
- 8. WASTE MATERIAL HANDLING 5**

APPENDIX A: Operational Plan and Profile Drawing(s)

APPENDIX B: ODOT Project Plan Sheets

1. Identification

Drainage Facility ID (DFI): **D00681**
Facility Type: Extended Detention Pond
Construction Drawings: (V-File Number) 46V-022
Location: District: 2B
Highway No.: 75
Mile Post: (6.00 to 6.06) Hwy 75, Left
Description: This facility is located northeast of the highway on the outside of the horizontal curve.

2. Facility Contact Information

Contact the Engineer of Record, Region Technical Center, or Geo-Environmental's Senior Hydraulics Engineer for:

- Operational clarification
- Maintenance clarification
- Repair or restoration assistance

Engineering Contacts:

Region Technical Center Hydro Unit Manager

Or

Geo-Environmental Senior Hydraulics Engineer (503) 986-3365.

3. Construction

Engineer of Record: Consultant Designer – [OBEC Consulting Engineers, Amy Jones, 971-634-2005]

Facility construction: 2014

Contractor: Kerr Contractors, Inc.

4. Storm Drain System and Facility Overview

An extended detention dry pond is a basin that is designed to detain stormwater for a sufficient time to allow particles and attached pollutants

to settle. The outlet control structure limits the rate of runoff leaving the pond by using an orifice. These facilities are designed to completely drain over a 48 hour period. The sizing of these facilities depends on the location and the amount of contributing impervious area.

This extended detention pond is designed to store runoff during wet weather and is dry the remainder of the time. It is located at the base of the eastern portion of the Camp Withycombe wooded hillside. Access to the facility is provided from the highway shoulder.



Figure 2: Location and Maintenance Access

There is one culvert and one ditch that convey stormwater runoff from offsite areas north and east of the Sunrise Corridor alignment into the detention pond. The locations of these are noted on the Operation Plan as points E and F in Appendix A.

This pond does not receive any runoff from the Sunrise Corridor. It is intended to control the runoff release rate into Cow Creek at the new outfall location as the contributing area originally entered Cow Creek via sheet flow, dispersing the peak runoff throughout the length of the Creek.

Runoff exits the pond by way of a Type “D” inlet connected to 12-inch storm drain pipe and a 6” underdrain that connect to a manhole containing the flow control assembly. See photo below and Points A, B and D on the Operational Plan in Appendix A.

The storm drain outlet pipe from the flow control manhole connects to the auxiliary outfall (Point C in Appendix A). The storm drain pipe from the auxiliary outfall is 24-inches in diameter and spans underneath the Sunrise Corridor. The receiving waterway for the outlet pipe is Cow Creek.




Figure 3: Detention Pond Outfalls

A. Maintenance equipment access:

The pond and outlet structures can be accessed from a maintenance access road connecting to the Sunrise Corridor. See maintenance access road layout on the Operational Plan in Appendix A

B. Heavy equipment access into facility:

- Allowed (no limitations)
- Allowed (with limitations)
- Not allowed

C. Special Features:

- Amended Soils
- Porous Pavers
- Liners
- Underdrains

5. Facility Haz Mat Spill Feature(s)

The pond can be used to store a volume of liquid by blocking the 12-inch diameter outlet pipe with the Type “D” inlet located at the outfall structure in the middle of the south side of the pond. This pipe is noted as point C in the Operational Plan. A barrier such as a metal plate over the metal grate on the inlet could be used to prevent liquid from draining from the pond. There is an underdrain system that will also need to be blocked by plugging the 6-inch pipe inlet in the flow control manhole.

6. Auxiliary Outlet (High Flow Bypass)

Auxiliary Outlets are provided if the primary outlet control structure cannot safely pass the projected high flows. Broad-crested spillway weirs and over flow risers are the two most common auxiliary outlets used in stormwater facility design. The auxiliary outlet feature is either a part of the facility or an additional storm drain feature/structure.

The auxiliary outlet feature for this facility is:

- Designed into facility
High flows exit the pond through the auxiliary outlet structure consisting of two type “D” inlets. These inlets connect to the outfall pipe from the main outfall and flow control structure. See Figure 3 above and the Operational Plan in Appendix A.
- Other, as noted below

There is an underdrain pipe system designed to provide infiltration for the pond.

7. Maintenance Requirements

Routine maintenance table for non-proprietary stormwater treatment and storage/detention facilities have been incorporated into ODOT's Maintenance Guide. These tables summarize the maintenance requirements for ponds, swales, filter strips, bioslopes, and detention tanks and vaults. Special maintenance requirements in addition to the routine requirements are noted below when applicable.

The ODOT Maintenance Guide can be viewed at the following website:

<http://www.oregon.gov/ODOT/HWY/OOM/MGuide.shtml>

Maintenance requirements for proprietary structures, such as underground water quality manholes and/or vaults with filter media are noted in Appendix C when applicable.

The following stormwater facility maintenance table (See ODOT Maintenance Guide) should be used to maintain the facility outlined in this Operation and Maintenance Manual or follow the Maintenance requirements outlined in Appendix C when proprietary structure is selected below:

- Table 1 (general maintenance)
- Table 2 (stormwater ponds)
- Table 3 (water quality biofiltration swales)
- Table 4 (water quality filter strips)
- Table 5 (water quality bioslopes)
- Table 6 (detention tank)
- Table 7 (detention vault)
- Appendix C (proprietary structure)
- Special Maintenance requirements

8. Waste Material Handling

Material removed from the facility is defined as waste by DEQ. Refer to the roadwaste section of the ODOT Maintenance Yard Environmental Management System (EMS) Policy and Procedures Manual for disposal options: <http://egov.oregon.gov/ODOT/HWY/OOM/EMS.shtml>




Contact any of the following for more detailed information about management of waste materials found on site:

ODOT Clean Water Unit	(503) 986-3008
ODOT Statewide Hazmat Coordinator	(503) 229-5129
ODOT Region Hazmat Coordinator	(503) 731-8290
ODEQ Northwest Region Office	(503) 229-5263

Appendix A

Content:

- **Operational Plan and Profile Drawing(s)**



LEGEND:

- (A) 6" Drainage Pipe Network
- (B) Flow Control Structure
- (C) Auxiliary Outlet Catch Basins (Type D)
- (D) Outlet Catch Basin (Type D)
- (E) 18" Inlet Pipe w/ Riprap Pad
- (F) Drainage Ditch (Inflow to Pond)
- ▨ Porous Pavers
- Storm Pipe (Facility)
- Storm Pipe
- Catch Basin
- Manhole
- ~ Stormwater Flow Path


Sheet 1 of 2

Prepared By:
Brooklyn Scholz

Drafted By:
Brooklyn Scholz

OREGON DEPARTMENT OF TRANSPORTATION

DFI D00681
MAINTENANCE DISTRICT 2B HWY 075
WATER QUALITY EXTENDED DETENTION DRY POND
 HIGHWAY MP 6.00 TO 6.06
 CLACKAMAS



Outlet Structure Detail
N.T.S.

Sheet 2 of 2

 OREGON DEPARTMENT OF TRANSPORTATION

Prepared By:
Brooklyn Scholz

Drafted By:
Brooklyn Scholz


DFI D00681
MAINTENANCE DISTRICT 2B HWY 075
WATER QUALITY EXTENDED DETENTION DRY POND
HIGHWAY MP 6.00 TO 6.06
CLACKAMAS

Appendix B

Content:

- **ODOT Project Plan Sheets (46V-022)**
 - *Cover/Title Sheet*
 - *Water Quality/Detention Plan Sheets*
 - *Other Details*

STATE OF OREGON
 DEPARTMENT OF TRANSPORTATION
 PLANS FOR PROPOSED PROJECT
**GRADING, DRAINAGE, STRUCTURES, PAVING, SIGNING,
 ILLUMINATION, SIGNALS & ROADSIDE DEVELOPMENT**



Overall Length Of Project - 3.90 Miles

INDEX OF SHEETS	
SHEET NO.	DESCRIPTION
1	Title Sheet
1A	Index Of Sheets Cont'd.

FFO - OR212/224: SUNRISE CORRIDOR (I-205 - SE 122ND AVE) SEC.

**CLACKAMAS HWY.
 CLACKAMAS COUNTY
 MARCH 2013**


**BEGIN WORK
 JTA-STP-S171(030)
 STA. "SR1" 505+78**

**BEGIN WORK
 JTA-STP-S171(030)
 STA. "G" 463+00**

**END WORK
 JTA-STP-S171(030)
 STA. "G" 492+00**

**END WORK
 JTA-STP-S171(030)
 STA. "OR" 352+20**

**END WORK
 JTA-STP-S171(030)
 STA. "T" 705+75**



ATTENTION:
 Oregon Law Requires You To Follow Rules Adopted By The Oregon Utility Notification Center. Those Rules Are Set Forth In OAR 952-001-0010 Through OAR 952-001-0090. You May Obtain Copies Of The Rules By Calling The Center. (Note: The Telephone Number For The Oregon Utility Center is (503) 232-1987.)

**LET'S ALL
 WORK TOGETHER
 TO MAKE THIS
 JOB SAFE**

- OREGON TRANSPORTATION COMMISSION**
- Pat Egan CHAIR
 - David Lohman COMMISSIONER
 - Mary F. Olson COMMISSIONER
 - Mark Frohnmayer COMMISSIONER
 - Tammy Boney COMMISSIONER
 - Matthew L. Garrett DIRECTOR OF TRANSPORTATION

PLANS PREPARED FOR
 OREGON DEPARTMENT OF TRANSPORTATION

OBEC CONSULTING ENGINEERS
 CORPORATE OFFICE: 920 COUNTRY CLUB ROAD, SUITE 100B EUGENE, OREGON 97401-0089
 REGIONAL OFFICES: LAKE OSWEGO, SALEM, MEDFORD, OREGON; VANCOUVER, WASHINGTON

These plans were developed using ODOT design standards. Exceptions to these standards, if any, have been submitted and approved by the ODOT Chief Engineer or their delegated authority.

Approving Authority: *Lawrence H. Fox* 12/31/12
 Signature & date


LAWRENCE H. FOX - PROJECT MANAGER
 Print name and title

Concurrence by ODOT Chief Engineer

**FFO - OR212/224: SUNRISE CORRIDOR (I-205 - SE 122ND AVE) SEC.
 CLACKAMAS HWY.
 CLACKAMAS COUNTY**

FEDERAL HIGHWAY ADMINISTRATION	PROJECT NUMBER	SHEET NO.
OREGON DIVISION	JTA-STP-S171(030)	1

SEC. 4, 5, 9, 10, 11
 T. 2 S., R. 2 E., W.M.



D00681
Detention Pond
SWM14

D00679
Detention Pond
SWM11

LEGEND
 No work area
 Regulated work area

REGISTERED PROFESSIONAL
ENGINEER
64332
Amy L. Jones
OREGON
NOVEMBER 14, 2000
AMY L. JONES
EXPIRES: 06/30/2013

OREGON DEPARTMENT OF TRANSPORTATION

OBEC CONSULTING ENGINEERS
 CORPORATE OFFICE:
920 COUNTRY CLUB ROAD, SUITE 100B EUGENE, OREGON 97401-6089
 REGIONAL OFFICES:
LAKE OSWEGO, SALEM, MEDFORD, OREGON; VANCOUVER, WASHINGTON
 www.obec.com

FFO - OR212/224: SUNRISE CORRIDOR (I-205 - SE 122ND AVE) SEC. CLACKAMAS HWY. CLACKAMAS COUNTY

Design Team Leader - Tom Metcalf
 Designed By - Ben Wewerka/Amy Jones
 Drafted By - Serban Dinca/Brittney Zornado


DRAINAGE & UTILITIES

SHEET NO.
11C



- ① See sht. 10D, note 6
Const. type "G-2" inlet
Inst. 12" storm sew. pipe
- ② See sht. 10D, note 26
Inst. 12" storm sew. pipe
- ③ See sht. 10D, note 27
Const. type "G-2" inlet
Inst. 12" storm sew. pipe
- ④ Sta. "SR2" 608+18.59, 66.11' Rt.
Const. storm manhole
Inst. 12" storm sew. pipe - 189'
10' depth
- ⑤ Sta. "SR2" 610+20.32, 67.9' Rt.
Const. type "G-2" inlet
Inst. 12" storm sew. pipe - 165'
10' depth
- ⑥ Sta. "SR2" 613+68.40, 68.4' Rt.
Const. type "G-2" inlet
Inst. 12" storm sew. pipe - 161'
5' depth
- ⑦ Sta. "SR2" 611 +96.32, 67.9' Rt.
Const. type "G-2" inlet
Inst. 12" storm sew. pipe - 16'
5' depth
- ⑧ Sta. "SR2" 611+96.47, 84.3' Rt.
Const. sedimentation manhole 72" dia.
Inst. 12" storm sew. pipe - 26'
5' depth
Const. sloped end
Const. paved end slope, Rt.
Const. riprap basin
(For details, see shts. GJ-14B & GJ-22)
- ⑨ Sta. "SR2" 610+70.49, 75.3' Lt.
Inst. 24" storm sew. pipe - 207'
20' depth
- ⑩ Sta. "SR2" 611+78.92, 102' Rt.
Const. storm manhole
Inst. 24" storm sew. pipe - 182'
5' depth
- ⑪ Sta. "SR2" 610+25.24, 21.9' Rt.
Const. type "G-2" inlet
Inst. 12" storm sew. pipe - 164'
5' depth
- ⑫ Sta. "SR2" 611+92.88, 21.9' Rt.
Const. type "G-2" inlet
Inst. 12" storm sew. pipe - 165'
5' depth
- ⑬ Sta. "SR2" 613+61.30, 21.9' Rt.
Const. type "G-2" inlet
Inst. 12" storm sew. pipe - 217'
5' depth
- ⑭ Sta. "SR2" 615+83.24, 21.9' Rt.
Const. type "G-2" inlet
Inst. 12" storm sew. pipe - 50'
5' depth

- ⑮ Sta. "SR2" 615+83.85, 72' Rt.
Const. type "G-2" inlet
Inst. 12" storm sew. pipe - 17'
5' depth
Const. sloped end
Const. paved end slope, Rt.
Const. riprap basin
(For details, see sht. GJ-22)
- ⑯ Sta. "SR2" 618+07.62, 21.9' Rt.
Const. type "G-2" inlet
Inst. 12" storm sew. pipe - 67'
5' depth
- ⑰ Sta. "SR2" 617+76.97, 82.52' Rt.
Const. type "G-2" inlet
Inst. 12" storm sew. pipe - 31'
5' depth
- ⑱ Sta. "SR2" 617+79.54, 109.9' Rt. to
Sta. "SR2" 617+91.07, 110.64' Rt.
Inst. 12" storm sew. pipe - 19'
5' depth
Const. sloped end
Const. paved end slope, Rt.
- ⑲ Sta. "SR2" 617+91.07, 110.64' Rt.
Const. storm manhole
Inst. 12" storm sew. pipe - 63'
5' depth
Const. sloped end
Const. paved end slope, Rt.
Const. riprap basin
(For details, see sht. GJ-22)
- ⑳ Sta. "SR2" 614+53.78, 95.78 Rt. to
Sta. "SR2" 615+64.37, 57.61' Lt.
Inst. 36" conc. culv. pipe - 188'
10' depth
Fill bottom 1/3 with compacted native soil
Culv. drainage marker, type 1
Culv. drainage marker, type 2
(For details, see sht. GJ-23)
(See drg. no. RD398)
- ㉑ Sta. "SR2" 614+64.21, 110.92' Rt. to
Sta. "SR2" 615+90.08, 69.37' Lt.
Inst. 71"x47" corr. metal arch culv. pipe - 218'
20' depth
Const. sloped end - 2
Const. paved end slope, Lt. & Rt.
Culv. drainage marker, type 1
Culv. drainage marker, type 2
(See drg. nos. RD304, RD319 & RD382)
- ㉒ Sta. "SR2" 615+78.94, 88.2' Rt. to
Sta. "SR2" 617+82.05, 101.7' Rt.
Const. ditch
"V" bottom, 1:3 slopes
Dt. exc. - 291 cu. yd.
(For details, see sht. GJ-25)
- ㉓ Const. storage pond, D00681 (SWM14)
Inst. facility field markers, type S1 - 2
Inst. facility field marker, type S2
Aggregate base - 475 tons
(For details, see sht. GJ-17)
- ㉔ Const. storage pond, D00679 (SWM11)
Inst. facility field markers, type S1 - 2
Inst. facility field marker, type S-2
Aggregate base - 225 tons
(For details, see sht. GJ-14)

- ㉕ Sta. "SR2" 610+65.28, 86.86' Lt. to
Sta. "SR2" 611+00.09, 80.68' Lt.
Inst. 18" culv. pipe - 38'
5' depth
Const. sloped end - 2
Const. paved end slope, Lt. & Rt.
Const. riprap basin
(For details, see sht. GJ-22)
- ㉖ Sta. "SR2" 611+16.49, 78.61' Lt. to
Sta. "SR2" 611+95.50, 78.13' Lt.
Inst. 18" culv. pipe - 85'
5' depth
Const. sloped end - 2
Const. paved end slope, Lt. & Rt.
- ㉗ See sht. 10D, note 22
Const. ditch
- ㉘ Inst. CIPP liner in extg. sanitary sew. pipe
(For details, see sht. SA-5)
- ㉙ Remove abandoned electrical lines & pole



OREGON DEPARTMENT OF TRANSPORTATION	
OBEC CONSULTING ENGINEERS www.obec.com	<small>CORPORATE OFFICE: 920 COUNTRY CLUB ROAD, SUITE 100B EUGENE, OREGON 97401-6089 REGIONAL OFFICES: LAKE OSWEGO; SALEM; MEDFORD, OREGON; VANCOUVER, WASHINGTON</small>
FFO - OR212/224: SUNRISE CORRIDOR (I-205 - SE 122ND AVE) SEC.	
CLACKAMAS HWY. CLACKAMAS COUNTY	
<small>Design Team Leader - Tom Metcalf Designed By - Ben Wewerka/Amy Jones Drafted By - Serban Dinca/Brittney Zornado</small>	
DRAINAGE & UTILITIES NOTES	SHEET NO. 11D



- ① 2 year WSE - 132.57
- ② 25 year WSE - 133.42
- ③ 50 year WSE - 133.57
- ④ 100 year WSE - 134.48
(Via emergency spillway only)



OREGON DEPARTMENT OF TRANSPORTATION



OBEC CONSULTING ENGINEERS
CORPORATE OFFICE:
920 COUNTRY CLUB ROAD, SUITE 100B EUGENE, OREGON 97401-6089
REGIONAL OFFICES:
LAKE OSWEGO; SALEM; MEDFORD, OREGON; VANCOUVER, WASHINGTON

FFO - OR212/224: SUNRISE CORRIDOR (I-205 - SE 122ND AVE) SEC.
CLACKAMAS HWY.
CLACKAMAS COUNTY



Design Team Leader - Tom Metcalf
Designed By - Ben Wewerka/Amy Jones
Drafted By - Serban Dinca/Brittney Zornado

STORMWATER DETAILS


SHEET NO. **GJ-17**




"SWM14" OUTFALL STRUCTURE DETAIL
DFI-D00681




"SWM14" FLOW CONTROL MANHOLE DETAIL
DFI-D00681




	CORPORATE OFFICE: 920 COUNTRY CLUB ROAD, SUITE 100B EUGENE, OREGON 97401-6089 REGIONAL OFFICES: LAKE OSWEGO; SALEM; MEDFORD, OREGON; VANCOUVER, WASHINGTON
FFO - OR212/224: SUNRISE CORRIDOR (I-205 - SE 122ND AVE) SEC. CLACKAMAS HWY. CLACKAMAS COUNTY	
Design Team Leader - Tom Metcalf Designed By - Ben Wewerka/Amy Jones Drafted By - Serban Dinca/Brittney Zornado	
STORMWATER DETAILS	SHEET NO. GJ-17A



"SWM14" AUXILIARY OUTFALL DETAIL
DFI-DO0681



"SWM14" DRAIN PIPE NETWORK DETAIL
DFI-DO0681



OREGON DEPARTMENT OF TRANSPORTATION	
OBEC CONSULTING ENGINEERS www.obec.com	<small>CORPORATE OFFICE: 920 COUNTRY CLUB ROAD, SUITE 100B EUGENE, OREGON 97401-6089 REGIONAL OFFICES: LAKE OSWEGO, SALEM, MEDFORD, OREGON; VANCOUVER, WASHINGTON</small>
FFO - OR212/224: SUNRISE CORRIDOR (I-205 - SE 122ND AVE) SEC.	
CLACKAMAS HWY. CLACKAMAS COUNTY	
Design Team Leader - Tom Metcalf Designed By - Ben Wewerka/Amy Jones Drafted By - Serban Dinco/Brittney Zornado	
STORMWATER DETAILS	SHEET NO. GJ-17B