

OPERATION & MAINTENANCE MANUAL

Water Quality Biofiltration Swale

Manual prepared: August 2020

DFI No. D01149




Figure 1: DFI No. D01149, looking [note cardinal direction]

Identification

Drainage Facility ID (DFI): D01149
Facility Type: Water Quality Biofiltration Swale
Construction Drawings: (V-File Numbers) 54V-010
Location: District: 1
Highway No.: 092
Mile Post: 25.890 to 25.910, [Left]

1. Manual Purpose

The purpose of this manual is to outline inspection needs and summarize maintenance actions.

2. Facility Location

The location map below details the facility location. The highway, mile posts, side streets, access location, and stormwater flow directions are noted on the map.

Facility location type: Roadway shoulder

Flow direction: North





Figure 2: Facility location map

3. Facility Summary

The length and width of a swale is based on the bottom dimensions.

The bottom length and bottom width of the swale is:


| Bottom Length (feet) | Bottom Width (feet) |
|----------------------|---------------------|
| 110 | 5 |



The depth of the swale is the vertical distance measured from the bottom of the swale to the top. The slope of the swale sides is presented by a vertical distance (rise) followed by the horizontal distance (run).

Depth and side slopes:

| Depth (feet) | Rise (feet) | Run (feet) |
|--------------|-------------|------------|
| Varies | 1 | 4 and 2 |



Site Specific Information: The swale take storm runoff from the adjacent road. The The foreslope has a 1:4 slope and the backslope has a 1:4 and a 1:2 slopes to meet existing grades.

4. Facility Access

Maintenance access to the facility:

| | |
|--|---|
| <input type="checkbox"/> Roadside pad | <input checked="" type="checkbox"/> Roadside shoulder |
| <input type="checkbox"/> Access road with Gate | <input type="checkbox"/> Access road without Gate |



Figure 3: Access along shoulder

5. Operational Components / Maintenance Items

Classification

This facility is classified as an:

| | |
|---|---|
| <input checked="" type="checkbox"/> On-line Swale | <input type="checkbox"/> Off-line Swale |
| A swale that does not include a high flow bypass component; flow drains into and through the facility | A swale that treats low/small flows and diverts high flows using a bypass component |

Bypass Component

This facility includes a high flow bypass component:

| <input checked="" type="checkbox"/> No | <input type="checkbox"/> Yes |
|---|---|
| There is no bypass component. High flows drains into and through the facility | There is a bypass component. Only low/small flows drain into the swale. High flows are diverted around the swale using a bypass component |

Operational Components

A swale has many components that assist with treatment, conveyance, and reducing flow velocity to minimize erosion. The components in use can vary depending if the facility was designed to operate on-line or off-line. The facility components table (**Table 1**) has been provided to highlight the applicable components for this facility. The component is in use when the box contains an “x” (e.g.).

The Standard Operation Manual for Water Quality Biofiltration Swales (implemented March 2017) outlines facility operation, typical footprint configuration, and component definitions and details. A link to the manual is attached to the feature marker in TransGIS.

<https://gis.odot.state.or.us/TransGIS/>

Operational Plan

The applicable standard operational plan for this facility is:

| <input checked="" type="checkbox"/> Operational Plan A | <input type="checkbox"/> Operational Plan B | <input type="checkbox"/> Operational Plan C |
|--|--|---|
| An on-line swale with roadside ditches | An on-line swale with piped inlets and outlets | An off-line swale with a piped high flow bypass |
| A standard operational plan illustrates the general facility footprint configuration and explains the purpose of each facility component. Operational plans (A, B, C) are provided in the Standard Operation Manual. | | |

See Appendix A for the site specific operational plan.

Maintenance Items

Operational components marked in **Table 1** should be inspected and maintained according to Section 7. Each facility component is defined and detailed in the Standard Operation Manual using the associated ID number indicated below.

| Table 1: Swale Components | | ID # |
|--|-------------------------------------|-------------|
| Manholes/Structures | | |
| Pre-treatment manhole | <input type="checkbox"/> | S1 |
| Weir type flow splitter/flow splitter manhole | <input type="checkbox"/> | S2 |
| Orifice type flow splitter/flow splitter manhole | <input type="checkbox"/> | S3 |
| Standard manhole | <input type="checkbox"/> | S4 |
| Swale Inlet | | |
| Pavement sheet flow | <input checked="" type="checkbox"/> | S5 |
| Inlet Pipe (s) | <input type="checkbox"/> | S6 |
| Open channel inlet | <input checked="" type="checkbox"/> | S7 |
| Riprap pad | <input checked="" type="checkbox"/> | S8 |
| Ground Cover | | |
| Grass bottom | <input checked="" type="checkbox"/> | S9 |
| Grass side slopes | <input checked="" type="checkbox"/> | S10 |
| Granular drain rock | <input type="checkbox"/> | S11 |
| Plantings | <input type="checkbox"/> | S12 |
| Underground Components | | |
| Geotextile fabric | <input type="checkbox"/> | S13 |
| Water quality mix | <input checked="" type="checkbox"/> | S14 |
| Perforated pipe | <input type="checkbox"/> | S15 |
| Porous pavers (access grid) | <input type="checkbox"/> | S16 |
| Flow Spreader | | |
| Rock basin (used at inlet) | <input type="checkbox"/> | S17 |
| Anchored board (midpoint of swale or every 50 feet along swale bottom) | <input type="checkbox"/> | S18 |
| Other: Riprap flow spreader | <input checked="" type="checkbox"/> | S19 |
| Swale Outlet | | |
| Catch basin with grate | <input type="checkbox"/> | S20 |
| Outlet Pipe (s) | <input type="checkbox"/> | S21 |
| Open channel outlet | <input checked="" type="checkbox"/> | S22 |
| Auxiliary Outlet: | <input type="checkbox"/> | S23 |
| Outfall Type | | |
| Waterbody (Creek/Lake/Ocean) | <input type="checkbox"/> C | S24 |
| | <input type="checkbox"/> L | |
| | <input type="checkbox"/> O | |
| Ditch | <input type="checkbox"/> | S25 |
| Storm drain system | <input type="checkbox"/> | S26 |

| Outfall Components | | |
|------------------------|--------------------------|------------|
| Riprap pad | <input type="checkbox"/> | S27 |
| Riprap bank protection | <input type="checkbox"/> | S28 |

6. Maintenance

Maintenance Frequency/Maintain Records

- Inspect annually. Preferably prior to the rainy season.
- Clean and maintain as necessary. Refer to Activity 125 for conditions when maintenance is needed.
- Keep a record of inspections, maintenance, and repairs.

Maintenance Guide/Maintenance Actions

The ODOT Routine Road Maintenance Water Quality and Habitat Guide (the *Blue Book*) outlines the standard maintenance actions for water quality facilities under Activity 125.

There are standard maintenance tables for standard ODOT designs. The maintenance tables describe the maintenance component, the defect or problem, the condition when maintenance is needed, and the recommended maintenance to correct the problem. Use the following tables to maintain ODOT swales:

- Table 1 (General Maintenance): Contains general maintenance and inspection guidelines that are applicable to all ODOT water quality facilities
- Table 3 (Maintenance of Water Quality or Biofiltration Swales): Contains maintenance information for swales

The *Blue Book* can be viewed at the following website:

http://www.oregon.gov/ODOT/Maintenance/Documents/blue_book.pdf

7. Limitations

Access grid installed:

| | |
|---|-------------------------------------|
| <input checked="" type="checkbox"/> No | <input type="checkbox"/> Yes |
| There are no porous pavers installed in this swale | |

Swales are designed to allow equipment access along the bottom. If an access grid is **NOT** installed, vehicles entering the swale can create depressions (tire ruts), damage vegetation, and damage structural components (e.g. flow spreaders). These conditions may result in poor treatment and drainage performance.

Equipment wheels should be kept on the tops and side slopes. Mower arms may be run along the swale bottom.

8. Waste Material Handling

Material removed from the facility is defined as waste by the Department of Environmental Quality (DEQ). Refer to the roadwaste section of the ODOT Maintenance Yard Environmental Management System (EMS) Policy and Procedures Manual for disposal options:

http://www.oregon.gov/ODOT/Maintenance/Documents/ems_manual.pdf


Contact any of the following for more detailed information about management of waste materials found on site:

| | |
|-----------------------------------|----------------|
| ODOT Clean Water Unit | (503) 986-3008 |
| ODOT Statewide Hazmat Coordinator | (503) 667-7442 |
| ODOT Region 1 Hazmat Coordinator | (503) 731-8290 |
| ODOT Region 2 Hazmat Coordinator | (503) 986-2647 |
| ODOT Region 3 Hazmat Coordinator | (541) 957-3594 |
| ODOT Region 4 Hazmat Coordinator | (541) 388-6186 |
| ODOT Region 5 Hazmat Coordinator | (541) 963-1590 |
| ODEQ Northwest Region Office | (503) 229-5263 |

A Appendix A – Site Specific Operational Plan

Contents:

Operational Plan: DFI D01149



- LEGEND:**
- Photo Location / Direction
 - Facility component (see table 1 in O&M Manual)
 - Biofiltration swale bottom
 - Adjacent system pipe
 - Conveyance direction
 - Pavement / facility flow path
 - Traffic flow direction

PLAN
No Scale

SECTION D-D
No Scale

SECTION B-B
No Scale

SECTION C-C
No Scale

SECTION A-A
No Scale

OREGON DEPARTMENT OF TRANSPORTATION

Prepared By:
Ramiro Perez

Drafted By:
Michael Skelton

DFI D01149
MAINTENANCE DISTRICT 1 HWY 092
BOIFILTRATION SWALE
HIGHWAY MP 25.89
COLUMBIA COUNTY

B Appendix B – Project Contract Plans

Contents:

Site Specific Subset of Project Contract Plan 54V-010

| INDEX OF SHEETS | |
|-----------------|-----------------------|
| SHEET NO. | DESCRIPTION |
| A01 | Title Sheet |
| A02 | Index Of Sheets Cont. |
| A03 | Std. Dwg. Nos. |


STATE OF OREGON
DEPARTMENT OF TRANSPORTATION

PLANS FOR PROPOSED PROJECT

**GRADING, DRAINAGE, PAVING, CURB RAMPS, SIGNING,
 ILLUMINATION, SIGNALS & ROADSIDE DEVELOPMENT**


**US30: MILLARD & BENNETT ROADS
 (ST. HELENS) SEC.**

**LOWER COLUMBIA HIGHWAY
 COLUMBIA COUNTY
 NOVEMBER 2020**



Overall Length Of Project - 1.44 Miles

ATTENTION:
 Oregon Law Requires You To Follow Rules Adopted
 By The Oregon Utility Notification Center.
 Those Rules Are Set Forth In OAR 952-001-0001
 Through OAR 952-001-0090.
 You May Obtain Copies Of The Rules By Calling
 The Center (Note: The Telephone Number For
 The Oregon Utility Notification Center Is
 (503) 232-1987).



OREGON TRANSPORTATION COMMISSION
 Robert Van Brocklin CHAIR
 Alando Simpson COMMISSIONER
 Martin Callery COMMISSIONER
 Julie Brown COMMISSIONER
 Sharon Smith COMMISSIONER
 Kristopher W. Strickler DIRECTOR OF TRANSPORTATION

These plans were developed using ODOT design standards. Exceptions to these standards, if any, have been submitted and approved by the ODOT Chief Engineer or their delegated authority.

Approving Authority: [Signature] Sep 17 2020 4:29 PM
 Signature & date

Vidal T. Francis-R2 Tech Center Manager
 Print name and title


[Signature] Sep 21 2020 11:22 AM
 Concurrence by ODOT Chief Engineer

T. 4 N., R. 1 W., W.M.



**US30: MILLARD & BENNETT ROADS
 (ST. HELENS) SEC.
 LOWER COLUMBIA RIVER HIGHWAY
 COLUMBIA COUNTY**

| | | |
|--------------------------------|----------------|-----------|
| FEDERAL HIGHWAY ADMINISTRATION | PROJECT NUMBER | SHEET NO. |
| OREGON DIVISION | S092(066) | A01 |



REGISTERED PROFESSIONAL
ENGINEER
81784
Sep 3 2020 3:27 PM
OREGON
JANUARY 8, 2009
CALVIN RAY LARWOOD


RENEWS: 12-31-2020

OREGON DEPARTMENT OF TRANSPORTATION

US30: MILLARD & BENNETT ROADS
(ST. HELENS) SEC.
LOWER COLUMBIA RIVER HIGHWAY
COLUMBIA COUNTY

Designer: Calvin Larwood Reviewer: Derryl James
Drafter: Charlotte Gerken Checker: N/A

ALIGNMENT SHEET NO.
C02



OREGON DEPARTMENT OF TRANSPORTATION

US30: MILLARD & BENNETT ROADS
(ST. HELENS) SEC.
LOWER COLUMBIA RIVER HIGHWAY
COLUMBIA COUNTY

Designer: Calvin Larwood Reviewer: Derryl James
Drafter: Charlotte Gerken Checker: N/A

GENERAL CONSTRUCTION SHEET NO. C02A

RENEWS: 12-31-2020

FINAL ELECTRONIC DOCUMENT
AVAILABLE UPON REQUEST

Rotation: 0° Scale: 1"=100'

① *Inst. multiple mailbox support
Const. conc. collar
(See dwg. nos. RD100 & RD101)*

⑪ *Inst. single mailbox support
Const. conc. collar*

② *Const. appr. - 2
(See dwg. no. RD715)*

⑫ *Const. Type "C" traffic separator
(For details, see shts. BB05 & BB06)*

③ *Const. Type "C" conc. Island, Non-mountable
(For details, see sht. BB05)*

⑬ *Const. Type "C" conc. Island, Non-mountable
(For details, see sht. BB06)*

④ *Const. Type "C" traffic separator
(For details, see sht. BB05)
(See dwg. no. RD706)*

⑭ *Const. R.R. crossing
USDOT Crossing #057924P
(By others)*

⑤ *Const. Type "C" traffic separator
(For details, see sht. BB05)*

⑮ *Const. ACP to conc. pmvt. transition
(For details, see sht. BB08)*


⑥ *Const. Type "C" conc. Island, Non-mountable
(For details, see sht. BB05)*

⑦ *Const. Type "C" traffic separator
(For details, see sht. BB05)*


⑧ *Const. Type "C" conc. Island, Non-mountable
(For details, see sht. BB06)*


⑨ *Sta. "OP"12+25.79 to Sta. "OP"13+55.56, Lt.
Const. midwest guardrail system- 118.2' (Type 2A)
Const. midwest guardrail system- 12.5' (Type 3)
Inst. end piece (Type B)
Const. anchor (Type 1) (Mod.)
Const. guardrail terminal, non-flared
Test level 3
(See dwg. nos. RD401, RD402, RD403, RD404,
RD407, RD416, RD417, RD419, RD420, RD445,
RD450, RD451 & RD482)*

⑩ *Sta. "L"905+98.44 to Sta. "L"907+01.34, Lt.
Const. midwest guardrail system- 58.5' (Type 2A)
Const. midwest guardrail system- 12.5' (Type 3)
Inst. end piece (Type B)
Const. anchor (Type 1) (Mod.)
Const. guardrail terminal, non-flared
Test level 3*



RENEWS: 12-31-2020

| | |
|---|--|
|  OREGON DEPARTMENT OF TRANSPORTATION | |
| US30: MILLARD & BENNETT ROADS (ST. HELENS) SEC. LOWER COLUMBIA RIVER HIGHWAY COLUMBIA COUNTY | |
| Designer: Calvin Larwood Drafter: Charlotte Gerken | Reviewer: Derryl James Checker: N/A |
| GENERAL CONSTRUCTION NOTES | |
| SHEET NO. C02B | |



Work zone fencing shown thus: - - - - -

REGISTERED PROFESSIONAL ENGINEER
81784
Sep 3 2020 3:30 PM
OREGON
JANUARY 8, 2009
CALVIN RAY LARWOOD
RENEWS: 12-31-2020

OREGON DEPARTMENT OF TRANSPORTATION

US30: MILLARD & BENNETT ROADS (ST. HELENS) SEC. LOWER COLUMBIA RIVER HIGHWAY COLUMBIA COUNTY

Designer: Calvin Larwood Reviewer: Derryl James
 Drafter: Charlotte Gerken Checker: N/A

DRAINAGE & UTILITIES

SHEET NO. C02C

- ① Remove pipe - 42'
Inst. 18" culv. pipe - 42'
5' depth
Inst. culv. ID marker, Type 2
DFI no D050109
MP 25.85
(See dwg. no. RD398)

- ② 24" culv. pipe - 130' (In pl.)
Extend - 28' Rt., 5' depth
Inst. culv. ID marker, Type 2
DFI no D029040
MP 25.76
Const. temp. water management facility
(See special provision 00245)

- ③ Remove pipe - 50'
Inst. 15" culv. pipe - 56'
5' depth


- ④ Const. water quality system - 3
(For sht. nos., see sht. A02, Hydraulic)

- ⑤ Sta. "L"908+08.5, 88' Lt.
Const. manhole, over extg. sew.
Connect to extg. culv. pipe
- ⑤A 24" culv. pipe - 130' (In pl.)
Extend - 26' Lt., 5' depth
Inst. 15" storm sew. pipe - 35'
5' depth
Inst. locator post
Const. temp. water management facility
(See special provision 00245)
(See dwg. no. RD334)

- ⑥ Remove pipe - 100'
Inst. 24" culv. pipe - 139'
5' depth
Inst. culvt. ID marker, Type 1 - 2
Const. temp. water management facility
(See special provision 00245)
(See dwg. no. RD398)


- ⑦ Sta. "BW"10+40, 25.8' Lt.
Remove inlet
Const. type "D" inlet
Remove pipe - 55'
Inst. 18" storm sew. pipe - 64'
5' depth
Const. sloped end
(See dwg. no. RD370)

- ⑧ Inst. 3" drain pipe - 730'
5'
- ⑧A Const. subsurface drain outlet - 7
(See dwg. no. RD312)



RENEWS: 12-31-2020

| | |
|---|--|
| OREGON DEPARTMENT OF TRANSPORTATION | |
| US30: MILLARD & BENNETT ROADS (ST. HELENS) SEC. LOWER COLUMBIA RIVER HIGHWAY COLUMBIA COUNTY | |
| Designer: Calvin Larwood Drafter: Charlotte Gerken | Reviewer: Derryl James Checker: N/A |
| DRAINAGE & UTILITIES NOTES | |
| SHEET NO. C02D | |




PLAN

- ① Sta. "S2" 899+93.90 to Sta. "S2" 900+99.60
Construct water quality swale - DFI no. D01149
Water Quality Soil Mix - 35 cu. yd.
Const. loose riprap (Class 50) - 16 cu. yd.
(For details, see sht. HA04)
- ② Sta. "L" 899+95
Inst. field facility marker, Type S1, Green
- ③ Sta. "L" 899+95
Inst. field facility marker, Type S2
- ④ Sta. "L" 900+98
Inst. field facility marker, Type S1, Red


NOTE:
Swale material estimated quantities
are listed in the Special Provisions.

* See riprap detail (Sht. HA01)




"S2" LINE SECTION

Scale: 1/8"=1'-0"
STA. "S2" 899+95.00 To STA. "S2" 900+94.60




"S2" LINE SECTION

Scale: 1/8"=1'-0"
STA. "S2" 899+90.00 To STA. "S2" 899+95.00
"S2" 900+94.60 To "S2" 900+99.60




PROFILE ALONG "S2" LINE

Horiz. Scale: 1"=30'
Vert. Scale: 1"=5'



| |
|---------------------|
| HWY: 000 |
| M.P.: 000.00-000.00 |
| COUNTY |
| Columbia |
| DFI/TSSU NO. |
| D01149 |

| | |
|---|------------------------------|
|  OREGON DEPARTMENT OF TRANSPORTATION | |
| US30: MILLARD & BENNETT ROADS (ST. HELENS) SEC. LOWER COLUMBIA RIVER HIGHWAY COLUMBIA COUNTY | |
| Designer: Ramiro Perez | Reviewer: Christopher Carman |
| Drafter: Jeff Coon | Checker: N/A |
| STORMWATER | |
| SHEET NO. HA02 | |