

# OPERATION & MAINTENANCE MANUAL

## Water Quality Biofiltration Swale

Manual prepared: July 2021

DFI No. D01332




Figure 1: DFI No. D01332, looking [note cardinal direction]

## Identification

Drainage Facility ID (DFI): D01332  
Facility Type: Water Quality Biofiltration Swale  
Construction Drawings: (V-File Numbers) 54V-111  
Location: District: 1  
Highway No.: 009 (US101)  
Mile Post: 9.19 to 9.21, Lt.

### 1. Manual Purpose

The purpose of this manual is to outline inspection needs and summarize maintenance actions.

### 2. Facility Location

The location map below details the facility location. The highway, mile posts, side streets, access location, and stormwater flow directions are noted on the map.

Facility location type: Roadway shoulder

Flow direction: West





Figure 2: Facility location map

### 3. Facility Summary

The length and width of a swale is based on the bottom dimensions.

The bottom length and bottom width of the swale is:


Bottom Length (feet)	Bottom Width (feet)
100	4



The depth of the swale is the vertical distance measured from the bottom of the swale to the top. The slope of the swale sides is presented by a vertical distance (rise) followed by the horizontal distance (run).

Depth and side slopes:

Depth (feet)	Rise (feet)	Run (feet)
Varies	1	4



**Site Specific Information:** The swale has a designed flat top 1' berms on each side then transitions at a 1:2 (Vertical: Horizontal) grade to match existing ground.

#### 4. Facility Access

Maintenance access to the facility:

<input type="checkbox"/> Roadside pad	<input checked="" type="checkbox"/> Roadside shoulder
<input type="checkbox"/> Access road with Gate	<input type="checkbox"/> Access road without Gate



Figure 3: Access along the shoulder

#### 5. Operational Components / Maintenance Items

##### Classification

This facility is classified as an:

<input checked="" type="checkbox"/> <b>On-line Swale</b>	<input type="checkbox"/> <b>Off-line Swale</b>
A swale that does not include a high flow bypass component; flow drains into and through the facility	A swale that treats low/small flows and diverts high flows using a bypass component

##### Bypass Component

This facility includes a high flow bypass component:

<input checked="" type="checkbox"/> <b>No</b>	<input type="checkbox"/> <b>Yes</b>
<b>There is no bypass component. High flows drain into and through the facility</b>	<b>There is a bypass component. Only low/small flows drain into the swale. High flows are diverted around the swale using a bypass component</b>

### Operational Components

A swale has many components that assist with treatment, conveyance, and reducing flow velocity to minimize erosion. The components in use can vary depending if the facility was designed to operate on-line or off-line. The facility components table (**Table 1**) has been provided to highlight the applicable components for this facility. The component is in use when the box contains an “x” (e.g.  ).

The Standard Operation Manual for Water Quality Biofiltration Swales (implemented March 2017) outlines facility operation, typical footprint configuration, and component definitions and details. A link to the manual is attached to the feature marker in TransGIS.

<https://gis.odot.state.or.us/TransGIS/>

### Operational Plan

The applicable standard operational plan for this facility is:

<input checked="" type="checkbox"/> <b>Operational Plan A</b>	<input type="checkbox"/> <b>Operational Plan B</b>	<input type="checkbox"/> <b>Operational Plan C</b>
<b>An on-line swale with roadside ditches</b>	<b>An on-line swale with piped inlets and outlets</b>	<b>An off-line swale with a piped high flow bypass</b>
<b>A standard operational plan illustrates the general facility footprint configuration and explains the purpose of each facility component. Operational plans (A, B, C) are provided in the Standard Operation Manual.</b>		

See Appendix A for the site specific operational plan.

### Maintenance Items

Operational components marked in **Table 1** should be inspected and maintained according to Section 7. Each facility component is defined and detailed in the Standard Operation Manual using the associated ID number indicated below.

<b>Table 1: Swale Components</b>		<b>ID #</b>
<b>Manholes/Structures</b>		
Pre-treatment manhole	<input type="checkbox"/>	<b>S1</b>
Weir type flow splitter/flow splitter manhole	<input type="checkbox"/>	<b>S2</b>
Orifice type flow splitter/flow splitter manhole	<input type="checkbox"/>	<b>S3</b>
Standard manhole	<input type="checkbox"/>	<b>S4</b>
<b>Swale Inlet</b>		
Pavement sheet flow	<input checked="" type="checkbox"/>	<b>S5</b>
Inlet Pipe (s)	<input type="checkbox"/>	<b>S6</b>
Open channel inlet	<input checked="" type="checkbox"/>	<b>S7</b>
Riprap pad	<input type="checkbox"/>	<b>S8</b>
<b>Ground Cover</b>		
Grass bottom	<input checked="" type="checkbox"/>	<b>S9</b>
Grass side slopes	<input checked="" type="checkbox"/>	<b>S10</b>
Granular drain rock	<input type="checkbox"/>	<b>S11</b>
Plantings	<input type="checkbox"/>	<b>S12</b>
<b>Underground Components</b>		
Geotextile fabric	<input type="checkbox"/>	<b>S13</b>
Water quality mix	<input checked="" type="checkbox"/>	<b>S14</b>
Perforated pipe	<input type="checkbox"/>	<b>S15</b>
Porous pavers (access grid)	<input type="checkbox"/>	<b>S16</b>
<b>Flow Spreader</b>		
Rock basin (used at inlet)	<input type="checkbox"/>	<b>S17</b>
Anchored board (midpoint of swale or every 50 feet along swale bottom)	<input type="checkbox"/>	<b>S18</b>
Other: Riprap flow spreader every 25'	<input type="checkbox"/>	<b>S19</b>
<b>Swale Outlet</b>		
Catch basin with grate	<input type="checkbox"/>	<b>S20</b>
Outlet Pipe (s)	<input type="checkbox"/>	<b>S21</b>
Open channel outlet	<input checked="" type="checkbox"/>	<b>S22</b>
Auxiliary Outlet: describe type	<input type="checkbox"/>	<b>S23</b>
<b>Outfall Type</b>		
Waterbody (Creek/Lake/Ocean)	<input type="checkbox"/> <b>C</b>	<b>S24</b>
	<input type="checkbox"/> <b>L</b>	
	<input type="checkbox"/> <b>O</b>	
Ditch	<input checked="" type="checkbox"/>	<b>S25</b>
Storm drain system	<input type="checkbox"/>	<b>S26</b>
<b>Outfall Components</b>		
Riprap pad	<input type="checkbox"/>	<b>S27</b>
Riprap bank protection	<input type="checkbox"/>	<b>S28</b>

## 6. Maintenance

### Maintenance Frequency/Maintain Records

- a. Inspect annually. Preferably prior to the rainy season.
- b. Clean and maintain as necessary. Refer to Activity 125 for conditions when maintenance is needed.
- c. Keep a record of inspections, maintenance, and repairs.

### Maintenance Guide/Maintenance Actions

The ODOT Routine Road Maintenance Water Quality and Habitat Guide (the *Blue Book*) outlines the standard maintenance actions for water quality facilities under Activity 125.

There are standard maintenance tables for standard ODOT designs. The maintenance tables describe the maintenance component, the defect or problem, the condition when maintenance is needed, and the recommended maintenance to correct the problem. Use the following tables to maintain ODOT swales:

- Table 1 (General Maintenance): Contains general maintenance and inspection guidelines that are applicable to all ODOT water quality facilities
- Table 3 (Maintenance of Water Quality or Biofiltration Swales): Contains maintenance information for swales

The *Blue Book* can be viewed at the following website:

[http://www.oregon.gov/ODOT/Maintenance/Documents/blue\\_book.pdf](http://www.oregon.gov/ODOT/Maintenance/Documents/blue_book.pdf)

## 7. Limitations

Access grid installed:

<input checked="" type="checkbox"/> No	<input type="checkbox"/> Yes
There are no porous pavers installed in this swale	

Swales are designed to allow equipment access along the bottom. If an access grid is **NOT** installed, vehicles entering the swale can create depressions (tire ruts), damage vegetation, and damage structural components (e.g. flow spreaders). These conditions may result in poor treatment and drainage performance.

Equipment wheels should be kept on the tops and side slopes. Mower arms may be run along the swale bottom.



## 8. Waste Material Handling

Material removed from the facility is defined as waste by the Department of Environmental Quality (DEQ). Refer to the roadwaste section of the ODOT Maintenance Yard Environmental Management System (EMS) Policy and Procedures Manual for disposal options:

[http://www.oregon.gov/ODOT/Maintenance/Documents/ems\\_manual.pdf](http://www.oregon.gov/ODOT/Maintenance/Documents/ems_manual.pdf)

Contact any of the following for more detailed information about management of waste materials found on site:







ODOT Clean Water Unit	(503) 986-3008
ODOT Statewide Hazmat Coordinator	(503) 667-7442
ODOT Region 1 Hazmat Coordinator	(503) 731-8290
ODOT Region 2 Hazmat Coordinator	(503) 986-2647
ODOT Region 3 Hazmat Coordinator	(541) 957-3594
ODOT Region 4 Hazmat Coordinator	(541) 388-6186
ODOT Region 5 Hazmat Coordinator	(541) 963-1590
ODEQ Northwest Region Office	(503) 229-5263


## **A Appendix A – Site Specific Operational Plan**

### **Contents:**


**Operational Plan: DFI D01332**

**LEGEND:**


-  Photo Location / Direction
-  Facility component (see table 1 in O&M Manual)
-  Storm facility boundary
-  Storm facility bottom
-  Pavement / facility flow path
-  Traffic flow direction



**PLAN**  
Not to Scale



**SECTION B-B**  
Not to Scale



**SECTION A-A**  
Not to Scale



OREGON DEPARTMENT  
OF TRANSPORTATION

Prepared By:  
Ramiro Perez

Drafted By:  
Michael Skelton

**DFI D01332**  
**MAINTENANCE DISTRICT 1 HWY 9**  
**WATER QUALITY BIOFILTRATION SWALE**  
OREGON COAST HWY MP 9.19  
CLATSOP COUNTY

## **B Appendix B – Project Contract Plans**

### **Contents:**

**Site Specific Subset of Project Contract Plan 54V-111**

INDEX OF SHEETS	
SHEET NO.	DESCRIPTION
A01	Title Sheet
A02	Index Of Sheets Cont. & Std. Dwg. Nos.

STATE OF OREGON  
DEPARTMENT OF TRANSPORTATION

PLANS FOR PROPOSED PROJECT


GRADING, DRAINAGE, PAVING, SIGNING & ILLUMINATION

**US101 @ PERKINS LANE INTERSECTION  
IMPROVEMENTS PROJECT**

OREGON COAST HIGHWAY

CLATSOP COUNTY

OCTOBER 2021




Overall Length Of Project - 0.41 Miles

**ATTENTION:**  
Oregon Law Requires You To Follow Rules Adopted By The Oregon Utility Notification Center. Those Rules Are Set Forth In OAR 952-001-0010 Through OAR 952-001-0090. You May Obtain Copies Of The Rules By Calling The Center. (Note: The Telephone Number For The Oregon Utility Center Is (503) 232-1987.)



**BEGINNING OF PROJECT**  
STA. "L" 249+46 (MP 9.18)

**END OF PROJECT**  
STA. "L" 271+60 (MP 9.59)



T. 7 & 8 N., R. 10 W., W.M.



OREGON TRANSPORTATION COMMISSION

- Robert Van Brocklin CHAIR
- Alando Simpson COMMISSIONER
- Julie Brown COMMISSIONER
- Sharon Smith COMMISSIONER
- Vacant COMMISSIONER
- Kristopher W. Strickler DIRECTOR OF TRANSPORTATION

These plans were developed using ODOT design standards. Exceptions to these standards, if any, have been submitted and approved by the ODOT Chief Engineer or their delegated authority.

Approving Authority: CAROL A. CARTWRIGHT Aug 23 2021 7:36 AM  
Signature & date

Carol A. Cartwright-R2 Tech Center Manager  
Print name and title


Steven B Cooley Aug 26 2021 8:38 AM  
Concurrence by ODOT Chief Engineer

**US101 @ PERKINS LANE INTERSECTION  
IMPROVEMENTS PROJECT**  
OREGON COAST HIGHWAY  
CLATSOP COUNTY


FEDERAL HIGHWAY ADMINISTRATION	PROJECT NUMBER	SHEET NO.
OREGON DIVISION	S009(504)	A01

PE002961 000

Sec. 33, T. 8N, R.10W, W.M.



"L"  
4°30'00" C.L.  
R 1273.240'  
TΔ 39°55'33"  
Ts 843.07'  
2 - 750' Sp.



**BEGINNING OF PROJECT**  
STA. "L" 249+46 (MP 9.18)

OREGON COAST HWY. (US101)

FT. STEVENS HWY. (OR104)

REGISTERED PROFESSIONAL  
ENGINEER  
85185PE  
Digitally Signed Aug 12 2021 4:51 PM  
OREGON  
NOV. 13, 2018  
NICOLAS DAVID THRASHER  
RENEWS: 06-30-2022

OREGON DEPARTMENT OF TRANSPORTATION



**US101 @ PERKINS LANE INTERSECTION IMPROVEMENTS PROJECT**  
OREGON COAST HIGHWAY  
CLATSOP COUNTY

Designer: Nicolas Thrasher      Reviewer: Calvin Larwood  
Drafter: Greg Malin              Checker: N/A


**ALIGNMENT**      SHEET NO. C01

FACILITY ID MARKER TABLE						
Facility Location		DFI Number	Type S2 Marker		Type S1 Marker	
Station	MP		Begin	End	Red	Green
"SW3" 00+61.00	9.19	D01332	✓	✓	✓	


✓ Check where appropriate  
 Red = Beginning of facility  
 Green = End of facility



- ① Sta. "SW3" 00+61.00 to Sta. "SW3" 1+61.00  
 Const. Water Quality Biofiltration Swale  
 DFI no. 01332  
 General excavation - 30 cu. yd.  
 Water Quality Soil Mix - 30 cu. yd.
- ② Sta. "SW3" 0+01.75 to Sta. "SW3" 0+61.00  
 Sta. "SW3" 1+61.00 to Sta. "SW3" 14+48.84  
 Const. Ditch  
 Ditch Excavation - 1900 cu. yd.
- ③ Inst. stormwater facility markers  
 (See dwg. RD399)




**TYPICAL SECTION**  
 STA. "SW3" 0+01.75 to STA. "SW3" 0+61.00  
 STA. "SW3" 1+61.00 to STA. "SW3" 14+48.84




**PROFILE ALONG "SW3" LINE**  
 Scale Horz.: 1"=100'  
 Scale Vert.: 1"=10'

NOTE:  
 Elevations shown are based on  
 North American Vertical Datum 1988 (NAVD88).



**TYPICAL SECTION**  
 STA. "SW3" 0+61.00 to STA. "SW3" 1+61.00


Note:  
 Slopes are shown as Vertical to Horizontal.




HWY: 009
M.P.: 9.19-9.48
UNIT FILE CODE
N/A
DFI/TSSU NO.
01332

RENEWS: 12-31-2022


OREGON DEPARTMENT OF TRANSPORTATION	
US101 @ PERKINS LANE INTERSECTION IMPROVEMENTS PROJECT OREGON COAST HIGHWAY CLATSOP COUNTY	
Designer: Ramiro Perez Drafter: Michael Skelton	Reviewer: Chris Carman Checker: N/A
STORMWATER PLAN	
SHEET NO. HA01	



① Sta. "SW3" 0+01.75 to Sta. "SW3" 0+61.00  
 Sta. "SW3" 1+61.00 to Sta. "SW3" 14+48.84  
 Const. Ditch  
 Ditch Excavation - 1900 cu. yd.



**TYPICAL SECTION**  
 STA. "SW3" 0+01.75 to STA. "SW3" 0+61.00  
 STA. "SW3" 1+61.00 to STA. "SW3" 14+48.84



**PROFILE ALONG "SW3" LINE**


HORIZ. SCALE: 1"=100'  
 VERT. SCALE: 1"=10'

NOTE:  
 Elevations shown are based on  
 North American Vertical Datum 1988 (NAVD88).

Note:  
 Slopes are shown as Vertical to Horizontal.



RENEWS: 12-31-2022

OREGON DEPARTMENT OF TRANSPORTATION 	
<b>US101 @ PERKINS LANE INTERSECTION IMPROVEMENTS PROJECT</b> OREGON COAST HIGHWAY CLATSOP COUNTY	
Designer: Ramiro Perez Drafter: Michael Skelton	Reviewer: Chris Carman Checker: N/A
<b>STORMWATER PLAN</b>	SHEET NO. HA02