SECTION 00641 - AGGREGATE SUBBASE, BASE, AND SHOULDERS

(Follow all instructions and make all edits with "Track Changes" turned on. If there are no instructions [orange text] above a subsection, paragraph, sentence, or bullet, then include it in the Project. Delete all orange text before preparing the final document. All other modifications to this Section will require ODOT Technical Resource and State Specifications Engineer approval.)

~~***(Use the following lead-in paragraph when none of the following subsections are included in the Project.)***~~

~~Comply with Section 00641 of the Standard Specifications.~~

~~***(Use the following lead-in paragraph when any of the following subsections are included in the Project.)***~~

Comply with Section 00641 of the Standard Specifications modified as follows:

(Use the following subsection .10 only when the Contractor has the option of using more than one size of Base Aggregate. Specify sizes in the blanks. Do not use this subsection when the Base Aggregate size is included in the Pay Item name.)

00641.10(a) Base and Shoulder Aggregate - In the paragraph that begins "Aggregate for bases…", add the following sentence after the first sentence:

Base Aggregate shall be either _____ or _____ size.

(Use the following subsection .20 when plant mix only is required.)

00641.20 Mixing Plant - Replace the sentence that begins "Mix Aggregate and water…" with the following two sentences:

Mix Aggregate and water according to subsection 00641.20(a). Road mix is not allowed on this Project.

(Use the following subsection .41 when plant mix only is required.)

00641.41 Mixing, Hauling, and Placing - Replace the sentence that begins "Add water to the Aggregate…" with the following two sentences:

Add water to the Aggregate while mixing to provide a moisture content according to 00641.12 and subsection 00641.41(a). Road mix is not allowed on this Project.

Add the following subsection:

00641.46 Small, Irregular Areas – Haul, place, shape and compact small irregular areas according to 00640.41 through 00640.43. A small or irregular area is outside of the Traveled Way and requires no more than 5 Tons of Aggregate Base or as otherwise approved by the Engineer.

In areas not accessible to the Equipment specified in 00641.24, use a weighted roller, vibratory plate compactor, tamping rammer compactor, or other approved Equipment suitable for the area as approved by the Engineer.