

AASHTOWare Daily Work Report DWR Demo

Anita Muhly, P.E.
Resident Engineer – Consultant Projects
AWP DWR & Diaries Subcommittee Team Lead
Anita.MUHLY@odot.oregon.gov
Cell: 971-403-8522

January 18, 2023

Best way to Contact: Teams Chat!



Agenda:


- 10 Min DWR Benefits**
- 25 Min GDPR to DWR Demo**
- 5 Min DWR Continued Resources**
- >10 Min Questions**



DWR Benefits

- **No more Pay Notes!**
 - DWR holds all info for Payment to the Contractor
 - Daily information = more important, but end of the month pay notes do not exist
- **DWR's completed offline: Mobile Inspector**
 - No service = No Problem
- **Immediate shared information, Reports!**
 - DWR's from other inspectors are viewable to all, even in Draft form
- **Combined Databases**
 - QPL, EquipmentWatch, Certifications, and more to come

GDPR to DWR Demo



General Daily Progress Report

Print Form

Project Information

DWR Testing 02 ACM 12345

Project Name (Default) Contract No.

US30 Lower Columbia Highway S092(066)

Highway Federal Aid No.

Siegmund Excavation & Construction Inc. Joe Smith Supervisor Present? Yes No

Contractor / Subcontractor On-Site Supervisor

Weather

Clear	Fair	Cloudy	Shower	Rain	Snow
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
TEMP	10-32	32-50	50-70	70-83	Over 83
	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
WIND	Still	Low	Med	High	
	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
HUMIDITY	Dry	Low	Med	High	
	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Number of Personnel and Major Equipment Reset

The first four columns are fixed and cannot be changed. In each of the remaining columns, please enter a heading specific to your job (e.g., Trainees, Backhoe, Flaggers) and record the numbers used by each contractor or sub.

Operations	Truck/Drivers	Laborers	TCS	F50	F250	F250											
1																	
		2	1	1	1												

Location and/or Description of Work Estimated Quantities

Add Item		Item No.	This Date	Total
STA 1+00 to 8+00	Delimiters, Type 1	0420	10	30
STA 1+00 to 8+00	MP Marker Posts	0430	2	22
STA 1+00 to 8+00	TMA - Truck Mounted	0150	1	1
Various	TCS	0040	1	6

Temporary Traffic Control Photo(s) Yes No

All traffic control items have been inspected and found to be satisfactory Yes No (if no, explain below)

Contractor installed Cones on the shoulder of the roadway from STA 1+00 to 8+00 on US30. TMA is used to protect shoulder work in areas where no guardrail is installed. Shoulder width maintained for TPAR access.

Equipment Photo(s) Yes No

Impact Attenuator Truck, F150, F250

Effects on Work (weather, accidents, breakdowns, delays, personnel, etc.) Photo(s) Yes No

Traffic Control Issue, discussed TPAR bike lane access issue on shoulder. Baker Rock corrected issue and resumed work after 1 hour.

Anita Muhly 50661

Prepared by Signature

Day Sunday Monday Tuesday Wednesday Thursday Friday Saturday 17-Jan-23

734-3474 (11-08-2018) Work Date



Contract Daily Work Report Summary

Contract: DWR Testing 02 ACM - Building data for DWR

DWR Date: 01/17/2023 Inspector: hwy41x Sequence: 1 Status: Draft

General

Notes

Contract Time

Contractors On Site

Contractor Equipment

Contractor Personnel

Contractor Staff

Agency Staff

Postings

Acceptance Records

Force Account Contractors

DWR Date * 01/17/2023

Inspector * hwy41x
Muhly Anita

Weather Light Rain - Rain Less than 1/2 inch

Rainfall Amount 0.25

Low Temperature 50

High Temperature 70

Stormwater Event No

Contractors Onsite Yes

Daily Staff Onsite Yes

Remarks

4

Federal Project Number S092(066)

State Project Number

Entered By hwy41x - Anita Muhly

Entered Date 01/17/2023 9:48:06 PM

Approval Date

Approved By

Payment Est Num

Payment Est Status

Agency Views

Remarks

Type *	Remark *	Created Dt
Effects on Work - Accidents, Breakdowns, Delays, etc...	Traffic Control issue; discussed TPAR bike lane access issue on shoulder. Baker Rock corrected issue and resumed work after 1 hour.	01/17/2023 10:32:02 PM
TC - Temporary Traffic Control	Contractor installed Cones on the shoulder of the roadway from STA 1+00 to 8+00 on US30. TMA is used to protect shoulder work in areas where no guardrail is installed. Shoulder width maintained for TPAR access.	01/17/2023 10:32:02 PM
Rejected Items - Materials, Equipment, etc...	None	01/17/2023 10:32:02 PM
DWRComment - DWR Comment	7:00 AM Inspector and Siegmund arrive on site. 8:00 AM Baker Rock Arrives on site.	01/17/2023 10:32:02 PM



DWR Continued Resources

DWR Subcommittee is **dedicated to making the Inspector's work easier**

- DWR's and Diaries Subcommittee every other Thursday from 2:00 PM – 3:00 PM
- Contact Vanessa or Anita

Mobile Inspector Demo

Topic: APOST Construction DWR & Diaries Subcommittee

Date: Mar 4, 2021 04:37 PM Eastern Time (US and Canada)

Copy the link below to share this recording with viewers:

<https://infotechinc.zoom.us/rec/share/Q78rgpH6Z622GhFz06RAKsKAuE-McNcTmncy10wBHtO2AixwXI-72yLqYqnhZlw.kNYY63Y6vobMIpQo>

Passcode: M5!.t6^P

Register for an AASHTOWare Account: <https://www.aashtowareproject.org/home>

Questions?

Anita Muhly, P.E.

Resident Engineer – Consultant Projects

AWP DWR & Diaries Subcommittee Team Lead

Anita.MUHLY@odot.oregon.gov

Cell: 971-403-8522

Best way to Contact: Teams Chat!

Contract Daily Work Report Summary

▼ Contract: DWR Testing 02 ACM - Building data for DWR

DWR Date: 01/17/2023 Inspector: hwye41x Sequence: 1

General	DWR Date * 01/17/2023
Notes	Inspector * hwye41x Muhly Anita
Contract Time	Weather Light Rain - Rain Less than 1/2 inch ▼
Contractors On Site	Rainfall Amount 0.25
Contractor Equipment	Low Temperature 50
Contractor Personnel	High Temperature 70
Contractor Staff	
Agency Staff	
Postings	
Acceptance Records	
Force Account Contractors	

