

## Basics

**Bothell:** Similar in size to Redmond, but more active real estate market due to metropolitan Seattle context

### Corridor/Project Description

- Conversion of 5-lane highway to a multi-way boulevard through downtown Bothell
- Part of sweeping downtown revitalization effort involving new park and new City Hall

### Client Jurisdictions

- City of Bothell (not a state highway, so able to avoid WSDOT design control)

### Timing

- Phase 1 in 2014 transformed the west side of Bothell Way between SR522 & Reder Way
- Phase 2 implemented 4 travel lanes, a left turn lane, two side medians with streetscaping, sidewalk and parking lanes
- Phase 3, just completed in 2017 was construction of multiway boulevard


### Cost, Funding

- \$13.4 million for Phase 2 & 3 multiway construction
- City's initial purchase of School District land was \$20.7 M – now selling that land to private developers
- Used City funds, State Transportation Improvement Bond (TIB) grants, developer contributions and proceeds from land sales

## Project Motivations

- Economic development was the primary focus; City wanted to revitalize their downtown
- Existing streetscape did not connect eastside (a historic main street) to westside (previously school district property) – contributing to stagnant-feeling downtown
- No existing bike lanes and little separation between through-traffic on the main arterial from pedestrians on the sidewalk, resulting in a bad pedestrian/bike experience
- Final catalyst was when Northshore School District, owners of 18 west side acres, displayed interest in leaving and the City took the opportunity to proceed

## Maps



### City of Bothell

- Population 44,546
- Fast-growing northern suburb of Seattle

## Engagement

- Strong public-facing educational and promotional component, including website
- Planning phase was more internal – across city staff and leadership
- More focused on individual public-private partnership discussions with prospective developers than open house public meetings

## Economic Development Coordination

- Unlike other cases, Bothell considered this project primarily as an economic revitalization project, with the transportation improvements just one of many ways to realize that plan
- Redevelopment was highly coordinated with the transportation planning throughout the project

## Design Elements

### Access Changes

- Previous roadway was limited-access highway, so no access points removed for multiway project itself
- Added one-way frontage road with controlled access points, separated from arterial lanes
- All businesses on the west now accessed via the side roads rather than the main arterial

### ROW Expansion

- ROW grew from 85 ft. to 152 ft., all added to west side
- Eastside ROW boundary kept to preserve historic structures

### Medians

- Added one small landscaped center median

### Bike/Pedestrian

- Bike racks and "sharrows" on frontage roads (shared road).

### Sidewalks

- 14-foot sidewalks from SR 522 to Reder Way

### Parking

- Parking was primarily in surface parking lots before.
- City took all parking off the main arterial and lined the access roads with at least one side of parallel parking (both sides where space allowed)
- New development encouraged to build structured parking

### Traffic Management, Signalization

- Four signalized intersections, intelligent transportation system interconnects all signals on NE Bothell Way

### Streetscape, Lighting, Aesthetics

- Street trees, landscape buffer strips, street furniture, trash bins
- Increased allowable height and created new design standards, (incl. lighting, sidewalks, branding, etc.)
- Ground floor retail required in multistory developments

## Economic Outcomes

- Project was followed by significant development and redevelopment activity
- New City Hall built on east side (City in talks with Marriott for adjacent hotel project)
- Several mixed-use residential-over-retail projects on west side parcels
- Bothell market is significantly stronger than Redmond's, allowing for high density land uses and high return-on-investment

## Other Outcomes

- Increase in pedestrian and bike activity
- Corridor now sets the tone for new development
- Seen as successful in creating a "seam" rather than an edge separating east and west sides of downtown

## Contacts

### Steve Morikawa

Capital Division Manager, City of Bothell,  
steven.morikawa@bothellwa.gov; 425-806-6820

### Ryan Roberts

Supervising Capital Project Engineer,  
ryan.roberts@bothellwa.gov; 425-806-6823

## Lessons Learned

- Multiway boulevard design is very flexible, allowing very different uses block by block
- Integrated approach between the overall downtown revitalization project and this central transportation piece seen as key to economic success
- By wiping the slate clean and introducing new code along with transportation piece, City was able to market a "whole package" to developers
- The City's level of coordination and control for this project would be difficult to match in Redmond, however, given that Bothell was able to avoid DOT involvement



## Basics

**Buena Vista:** Population 2,778; mountain town on Colorado's "Western Slope"

### Corridor Description

- Two miles of US Highway, primary (and only) regional access into and through town's Main Street area

### Design Prime Contractor

- David Evans & Associates

### Client Jurisdictions

- CDOT
- City of Buena Vista

### Timing

- Five-year design phase beginning 2012
- Construction phase 2016-17

### Cost, Funding

- \$11 million total costs (\$8 million for construction)
- Incl. \$500K partnership funding from Town and \$2 million RAMP access grant for "additional enhancements" incl. drainage & pedestrian

## Project Motivations

- Insufficient pedestrian and bike infrastructure
- Higher crash density at Brookdale and Main
- Projected decline in level of service at all intersections with projected growth in traffic through 2035
- "Built like a drag strip"-high speed traffic an issue
- Drainage & flood events caused many problems

## Contacts


**Lisa Schantes**, CDOT Region 5 Communications Manager, [lisa.schwantes@state.co.us](mailto:lisa.schwantes@state.co.us), 970-385-1428

**Phillip Puckett**, Buena Vista Town Administrator, [bvadmin@buenavistaco.gov](mailto:bvadmin@buenavistaco.gov), 719-395-8643

**Robert Burch**, Project Manager, Ground Engineering, [robert.burch@groundeng.com](mailto:robert.burch@groundeng.com), 303-289-1989

**LaSheita Sayer**, Project Public Information Manager, [LaSheita@zozogroup.com](mailto:LaSheita@zozogroup.com), 720-949-2020

## Maps



## Economic Development Coordination

- Economic development efforts were focused on Main Street and the City's industrial area (not project area)
- Took a "wait & see" approach to economic development efforts on the highway corridor, pending project results
- City will handle economic development efforts going forward (originally thought County might assist)

## Design Elements

### Access Changes

- Each access point examined: some closed, some changed to right-in and/or right-out only
- Dedicated driveways to businesses, generally retained one access point for each business on corridor

### Medians

- 4 short concrete medians (as pedestrian refuges & clear divisions between highway lanes)
- Additional medians identified in 2014 access plan as potential future projects pending funding

### Bike/Pedestrian

- Defined pedestrian crosswalks.
- Bike lanes on both northbound and southbound, marked by green paint.
- Bike boxes at intersections (public educated on how to use them through press releases, articles, etc.)

### Sidewalks

- New curbs & updated pedestrian crosswalks, including four new striped crossing locations with rapid rectangular flashing beacons (RRFBs) to provide pedestrians a designated place to cross the highway.
- Sidewalks along US 24 with ADA ramps at intersections.
- New five-foot sidewalks replaced some of the original walkways, including some narrow existing dirt trails.

### Parking

- Added 9-10 parallel parking spaces on Charles Street and 22-23 spaces on US 24, including near parks

### Traffic Management, Signalization

- Improved electronic intersection signalization at Main Street & US 24 (detection technology for emergency vehicles)

### Streetscape, Lighting, Aesthetics

- Relocation & upgrades to street lighting
- Design look/feel in keeping with town standards
- Monumentation/wayfinding to be addressed later phases (not funded in this phase)

## Economic Outcomes

- Summer 2016 (before project start) was Town's largest ever sales tax generating period – (the primary revenue source in CO)
- Despite construction, sales tax in 2017 stayed at or above 2016 levels.
- Construction undoubtedly had temporary impacts on businesses, but generally much less severe than anticipated/feared.
- Minimal property acquisition/takings

## Other Outcomes

- Increase in pedestrian and bike activity – albeit after a period of getting acclimated to the new facilities
- Traffic efficiency has improved (mostly due to better traffic signals)
- Narrower lanes have lowered average traffic speeds, consistent with safety goals
- Drainage solutions handled poorly and still need to be resolved (City vs. contractor)

## Lessons Learned

- Ensure communication between City and DOT is transparent, clear, and allows for implementable actions
- An intensive community engagement effort is essential throughout the project, and may require working one-on-one with property owners
- Ensure property owners are educated on the boundaries of their property to help mitigate acquisition tensions
- Get consensus on fundamental goals very early in the process – to help resolve disputes around conflicting visions (e.g., in Buena Vista, those of young versus old residents)
- Concentrate on a seamless transition from design to implementation, with previously agreed upon and enforceable rules.



## Basics

**Shoreline:** Population 55,333, northern suburb of Seattle

### Corridor/Project Description

- Phased, 3-mile streetscape enhancement project on Aurora Avenue (WA Hwy 99E), eventually covering the length of Shoreline, north to south

### Client Jurisdictions

- City of Shoreline, WSDOT

### Timing

- Planning began as early as 1998 with extensive design studies and public involvement
- 4 implementation phases completed from 2007-2016

### Cost, Funding

- \$140 million total (approx. \$4,200 per linear foot)
- City paid about 20%, with remainder covered by complex combination of federal, state and county dollars (about 50 grants in total)

## Project Motivations

- High traffic volumes, lack of sidewalks, wide roadway made corridor an unofficial parking lot for businesses
- WSDOT declared corridor one of the most dangerous in state – many auto-pedestrian accidents Too many turn lanes, no pedestrian or bike facilities, car dealerships, and disorganized parking everywhere
- Impermeable surfaces over 97% of area blocked rainwater absorption, causing flooding, erosion, and pollution issues from runoff


## Contacts

**Dan Eernisse,**  
Economic Development Director, [deernisse@shorelinewa.gov](mailto:deernisse@shorelinewa.gov),  
206-801-2218

**Nytasha Sowers,**  
Project Manager, Transportation Services Manager,  
[nsowers@shorelinewa.gov](mailto:nsowers@shorelinewa.gov), 206-801-2481

**John F. Vicente,**  
Capital Projects Manager, [jvicente@shorelinewa.gov](mailto:jvicente@shorelinewa.gov),  
206-801-2474

## Maps



### City of Shoreline

- Population 55,333
- 9 miles north of downtown Seattle

## Engagement

- Initial (1998) design phases had intensive outreach & public involvement
- Project included a Citizen Advisory Task Force made up of representatives from the business community neighborhoods, and transit users
- City assumed responsibility for public engagement for Phase 1 with unsatisfactory results, so hired consultants to handle engagement for remaining phases – having a neutral “third party” was beneficial

## Economic Development Coordination

- While the original vision documents lists economic development as a goal, the project was initially conceived as mainly a response to safety, traffic, etc.
- Later phases more focused on economic development, including city-wide branding strategy
- By Phase 4, stakeholders in near-consensus that “everyone benefits from these improvements”

## Design Elements

### Access Changes

- Much more access control, although almost all businesses (or centers) retained at least one access point
- Sidewalks and curbs now act as access control (versus prior condition of an uncurbed access free-for-all).

### Medians

- Several new medians of various lengths and widths
- Median breaks to allow left turn lanes where appropriate

### Bike/Pedestrian

- Main element is paved multiuse trail parallel to Aurora Ave.
- No bike facilities on avenue itself, although City chose to raise trail and build bridge over road at 155<sup>th</sup> St. to maintain flow for bikes and pedestrians
- Pedestrian improvements otherwise limited to crosswalks at intersections (using contrasting pavers and painted markings).

### Sidewalks

- New and wider sidewalks, separated from roadway by landscaping.

### Parking

- ROW acquisition involved removal of many business parking stalls, but much of it replaced by more organized parking stalls (prior condition very unorganized and unmarked)

### Utilities/Infrastructure

- Green infrastructure implemented for stormwater management (bioswales, rain gardens in medians and planter strips)
- Laid empty conduit for future utilities throughout corridor.
- Fiber broadband along whole corridor length

### Streetscape, Lighting, Aesthetics

- Very streetscape-intensive (plantings, human-level lighting, banners)
- Wrote design code specific to fencing, lighting, signage, branding, etc.

## Economic Outcomes

- Generally seen as a major success for city businesses and development, despite initial focus on safety and traffic issues
- Some free-standing retail is in decline, particularly in “in between places” outside of strong anchored centers
- Separate analysis by Leland Consulting Group found that, compared to three-mile corridor to the south (similar to “before” condition in Shoreline) has seen far less development activity

## Other Outcomes

- Increase in pedestrian and bike activity
- Traffic efficiency has improved (mostly due to better traffic signals)
- Narrower lanes have lowered average traffic speeds
- Drainage solutions handled poorly and still needs to be resolved (City vs. contractor)

## Lessons Learned

- Initial pushback from community changed once first mile was complete – businesses saw the improvements, the tone changed to “how fast can I get it?”
- Phased implementation (as funding made available) helped ground the project in reality and convey fiscal sensibility
- City's comprehensive plan helped to concentrate public improvements in desired areas, so interested developers could see that frontage work was already done – helped create an market-responsive tone
- The term “Business Access Transit (BAT) lanes” versus “dedicated transit lanes” was more palatable to businesses
- Engage utility companies early to use the same stub-outs for future access
- Establish a baseline historical turnover rate for corridor businesses, so not all post-construction closures or relocations get blamed on the project



## Basics

**Madras:** Population 6,729; small town approximately 26 miles north of Redmond on US Highway 97

### Corridor Description

- Approximately 0.34 miles of US Highway, primary regional access through town

### Design Prime Contractor

- OTAK

### Client Jurisdictions

- ODOT
- City of Madras

### Timing

- Construction phase 2016-17

### Cost, Funding

- \$1,400,000 project, funded primarily by an ODOT Transportation Enhancement grant of \$1,238,960 in 2014 (increased from \$939,000 in 2009 to cover the increase in costs over that 5 year time period)
- City contributed remainder of funds for additional enhancements to pedestrian infrastructure, lighting, and landscaping

## Project Motivations


- Dangerous road, lack of pedestrian and bike infrastructure (no sidewalks)
- City wanted to improve the aesthetics of the corridor as an entry or gateway to Madras
- While ODOT's primary purpose was the roadway improvement for safety and throughput, the City utilized some funds to implement additional sidewalks, drainage, and other improvements to target increased economic development

## Contacts

**Jeff Hurd,**  
City of Madras, Public Works Director, jhurd@ci.madras.or.us,  
541-325-0309

**Charles M. Darling (Mike),**  
ODOT, Project Manager, charles.m.darling@odot.state.or.us,  
541-388-6329

## Maps



**City of Madras**

- Population 6,729
- 26 miles north of Redmond on Hwy 97

## Engagement

- The project managers made additional efforts to communicate every potential disruption and work around business demands, even if it meant the project took a little longer, helping to smooth public relations
- ODOT ultimately led the process, who gathered feedback from community through open houses, etc.
- The biggest concern for business owners is losing access to their properties. Access consolidation is a sensitive and fragile subject if not done correctly

## Economic Development Coordination

- ODOT's primary purpose for the roadway project was improvement of safety and throughput
- City utilized some additional funds to implement additional sidewalks, drainage, and other improvements to target increased economic development

## Design Elements

### Access Changes:

- Most businesses kept one primary access, while others were consolidated to improve overall flow
- ODOT primarily decided where accesses were to be consolidated based on spacing and typical standards

### Medians

- Small median, with pedestrian refuge requiring a right-turn-only design
- (Note: the median led to a lawsuit getting filed against ODOT by the trucking company for limiting the company's ability to turn left)

### Bike/Pedestrian

- Pedestrian refuges and crosswalks, bike lanes on both sides

### Sidewalks

- Previously non-existent sidewalks; added 6-foot sidewalks, curbs, and landscaping

### Parking

- Parallel parking in a small stretch on the west side of the road

### Traffic Management, Signalization

- Improved electronic intersection signalization at Main Street & US 24 (detection technology for emergency vehicles)

### Streetscape, Lighting, Aesthetics

- Landscaped strips with green stormwater infrastructure (bioswales)
- New lighting, consistent with the City design standards

## Economic Outcomes

- Very recent completion so no new development has occurred to date
- City is seeing new interest in some highway adjacent properties, though, and believes that prospective property owners beginning to appreciate a "development ready" lot with an attractive frontage and no additional required improvements

## Other Outcomes

- Main overall outcome is an improvement in the perception of Madras (both external and self-perception)
- Although the process has been gradual, people now notice the change – Madras not "just a dirty little town anymore"

## Lessons Learned

- Although businesses ultimately like the improvements that were made, they may have to adjust to making new efforts for upkeep (especially for sidewalks or landscaping that didn't pre-exist)
- Thus, it is important to have a flexible plan to transition responsibility from government to private property
- It is beneficial, to the extent feasible, to give all stakeholders (businesses, property owners, etc.) a direct role in the design of the collective frontage, as this grounds the design in reality and helps them to champion the effort
- ODOT's process for easements or ROW acquisition takes a long time, so it is best to start that process early – that said, ODOT is "pretty fair and reasonable" with acquisitions