

OPERATION & MAINTENANCE MANUAL

Water Quality Biofiltration Swale

Manual prepared: December 2019

DFI No. **D01207**



Figure 1: DFI No. D01207, looking North (Placeholder for future photo)

Identification

Drainage Facility ID (DFI): D01207
Facility Type: Water Quality Biofiltration Swale
Construction Drawings: (V-File Numbers) 52V-27
Location: District: 05
Highway No.: 069
Mile Post: 069 10.1: Southeast On-Ramp
MP 069 AP1 10.13 to 10.16

1. Manual Purpose

The purpose of this manual is to outline inspection needs and summarize maintenance actions.

2. Facility Location

The location map below details the facility location. The highway, mile posts, side streets, access location, and stormwater flow directions are noted on the map.

Facility location type: Interchange

Flow direction: East





Figure 2: Facility location map (Placeholder)

3. Facility Summary

The length and width of a swale is based on the bottom dimensions.

The bottom length and bottom width of the swale is:


Bottom Length (feet)	Bottom Width (feet)
120	12.33



The depth of the swale is the vertical distance measured from the bottom of the swale to the top. The slope of the swale sides is presented by a vertical distance (rise) followed by the horizontal distance (run).

Depth and side slopes:

Depth (feet)	Rise (feet)	Run (feet)
2	2	8



Site Specific Information:

Access this facility from Southeast Beltline On-Ramp Ramp (069 AP1); there are two bollards and a gate at the entrance to the maintenance road. The facility is a bioswale with riprap lined inlet and outlet basins. The outlet basin discharges through an open channel outlet to a “V” ditch discharging to a culvert under the on-ramp. The culvert discharges to the pond complex, that is partially within ODOT’s Right-of-Way.

4. Facility Access

Maintenance access to the facility:

<input type="checkbox"/> Roadside pad	<input type="checkbox"/> Roadside shoulder
<input checked="" type="checkbox"/> Access road with Gate	<input type="checkbox"/> Access road without Gate




Figure 3: Facility Access (Placeholder)

5. Operational Components / Maintenance Items

Classification

This facility is classified as an:

<input checked="" type="checkbox"/> On-line Swale	<input type="checkbox"/> Off-line Swale
A swale that does not include a high flow bypass component; flow drains into and through the facility	A swale that treats low/small flows and diverts high flows using a bypass component

Bypass Component

This facility includes a high flow bypass component:

<input checked="" type="checkbox"/> No	<input type="checkbox"/> Yes
There is no bypass component. High flows drain into and through the facility	There is a bypass component. Only low/small flows drain into the swale. High flows are diverted around the swale using a bypass component

Operational Components

A swale has many components that assist with treatment, conveyance, and reducing flow velocity to minimize erosion. The components in use can vary depending if the facility was designed to operate on-line or off-line. The facility components table (**Table 1**) has been provided to highlight the applicable components for this facility. The component is in use when the box contains an “x” (e.g.).

The Standard Operation Manual for Water Quality Biofiltration Swales (implemented March 2017) outlines facility operation, typical footprint configuration, and component definitions and details. A link to the manual is attached to the feature marker in TransGIS.

<https://gis.odot.state.or.us/TransGIS/>

Operational Plan

The applicable standard operational plan for this facility is:

<input checked="" type="checkbox"/> Operational Plan A	<input checked="" type="checkbox"/> Operational Plan B	<input type="checkbox"/> Operational Plan C
An on-line swale with roadside ditches	An on-line swale with piped inlets and outlets	An off-line swale with a piped high flow bypass
A standard operational plan illustrates the general facility footprint configuration and explains the purpose of each facility component. Operational plans (A, B, C) are provided in the Standard Operation Manual.		

See Appendix A for the site specific operational plan.

Maintenance Items

Operational components marked in **Table 1** should be inspected and maintained according to Section 7. Each facility component is defined and detailed in the Standard Operation Manual using the associated ID number indicated below.

Table 1: Swale Components		ID #
Manholes/Structures		
Pre-treatment manhole	<input type="checkbox"/>	S1
Weir type flow splitter/flow splitter manhole	<input type="checkbox"/>	S2
Orifice type flow splitter/flow splitter manhole	<input type="checkbox"/>	S3
Standard manhole	<input checked="" type="checkbox"/>	S4
Swale Inlet		
Pavement sheet flow	<input type="checkbox"/>	S5
Inlet Pipe (s)	<input checked="" type="checkbox"/>	S6
Open channel inlet	<input type="checkbox"/>	S7
Riprap pad	<input checked="" type="checkbox"/>	S8
Ground Cover		
Grass bottom	<input checked="" type="checkbox"/>	S9
Grass side slopes	<input checked="" type="checkbox"/>	S10
Granular drain rock	<input type="checkbox"/>	S11
Plantings	<input type="checkbox"/>	S12
Underground Components		
Geotextile fabric	<input checked="" type="checkbox"/>	S13
Water quality mix	<input checked="" type="checkbox"/>	S14
Perforated pipe	<input type="checkbox"/>	S15
Porous pavers (access grid)	<input checked="" type="checkbox"/>	S16
Flow Spreader		
Rock basin (used at inlet)	<input checked="" type="checkbox"/>	S17
Anchored board (midpoint of swale or every 50 feet along swale bottom)	<input checked="" type="checkbox"/>	S18
Other:	<input type="checkbox"/>	S19
Swale Outlet		
Catch basin with grate	<input type="checkbox"/>	S20
Outlet Pipe (s)	<input type="checkbox"/>	S21
Open channel outlet	<input checked="" type="checkbox"/>	S22
Auxiliary Outlet:	<input type="checkbox"/>	S23
Outfall Type		
Waterbody (Creek/Lake/Ocean)	<input type="checkbox"/> C	S24
	<input checked="" type="checkbox"/> L	
	<input type="checkbox"/> O	
Ditch	<input type="checkbox"/>	S25
Storm drain system	<input checked="" type="checkbox"/>	S26
Outfall Components		
Riprap pad	<input checked="" type="checkbox"/>	S27
Riprap bank protection	<input type="checkbox"/>	S28

6. Maintenance

Maintenance Frequency/Maintain Records

- a. Inspect annually. Preferably prior to the rainy season.
- b. Clean and maintain as necessary. Refer to Activity 125 for conditions when maintenance is needed.
- c. Keep a record of inspections, maintenance, and repairs.

Maintenance Guide/Maintenance Actions

The ODOT Routine Road Maintenance Water Quality and Habitat Guide (the *Blue Book*) outlines the standard maintenance actions for water quality facilities under Activity 125.

There are standard maintenance tables for standard ODOT designs. The maintenance tables describe the maintenance component, the defect or problem, the condition when maintenance is needed, and the recommended maintenance to correct the problem. Use the following tables to maintain ODOT swales:

- Table 1 (General Maintenance): Contains general maintenance and inspection guidelines that are applicable to all ODOT water quality facilities
- Table 3 (Maintenance of Water Quality or Biofiltration Swales): Contains maintenance information for swales

The *Blue Book* can be viewed at the following website:

http://www.oregon.gov/ODOT/Maintenance/Documents/blue_book.pdf

7. Limitations

Access grid installed:

<input type="checkbox"/> No	<input checked="" type="checkbox"/> Yes
Medium Duty Porous Pavers	

Swales are designed to allow equipment access along the bottom. If an access grid is **NOT** installed, vehicles entering the swale can create depressions (tire ruts), damage vegetation, and damage structural components (e.g. flow spreaders). These conditions may result in poor treatment and drainage performance.

Equipment wheels should be kept on the tops and side slopes. Mower arms may be run along the swale bottom.

8. Waste Material Handling

Material removed from the facility is defined as waste by the Department of Environmental Quality (DEQ). Refer to the roadwaste section of the ODOT Maintenance Yard Environmental Management System (EMS) Policy and Procedures Manual for disposal options:

http://www.oregon.gov/ODOT/Maintenance/Documents/ems_manual.pdf


Contact any of the following for more detailed information about management of waste materials found on site:

ODOT Clean Water Unit	(503) 986-3008
ODOT Statewide Hazmat Coordinator	(503) 667-7442
ODOT Region 1 Hazmat Coordinator	(503) 731-8290
ODOT Region 2 Hazmat Coordinator	(503) 986-2647
ODOT Region 3 Hazmat Coordinator	(541) 957-3594
ODOT Region 4 Hazmat Coordinator	(541) 388-6186
ODOT Region 5 Hazmat Coordinator	(541) 963-1590
ODEQ Northwest Region Office	(503) 229-5263

A Appendix A – Site Specific Operational Plan

Contents:

Operational Plan: DFI D01207



- LEGEND:**
- (S#) Swale Component (See Table 1 in O&M Manual)
 - Manhole
 - Inlet
 - Storm Pipe (Facility)
 - - - Conveyance Direction
 - ▲ Pavement / Facility Flow Path
 - ↔ Highway Lane Direction


PLAN
N.T.S.

Sht. 1 of 2


OREGON DEPARTMENT OF TRANSPORTATION

DFI D01207
MAINTENANCE DISTRICT 05 HWY OR569
WATER QUALITY BIOFILTRATION SWALE
 BELTLINE HIGHWAY
 LANE COUNTY


Prepared By: R. Attenasio
 Drafted By: M. Wainwright




SECTION A-A
N.T.S.



V - DITCH
N.T.S.



FLOW SPREADER
N.T.S.



RIPRAP BASIN
N.T.S.

B Appendix B – Project Contract Plans

Contents:

Site Specific Subset of Project Contract Plan 52V-27

STATE OF OREGON
DEPARTMENT OF TRANSPORTATION

PLANS FOR PROPOSED PROJECT

GRADING, DRAINAGE, STRUCTURES, PAVING, SIGNING, ILLUMINATION,
SIGNALS, ITS & ROADSIDE DEVELOPMENT

OR569: BELTLINE @


DELTA HIGHWAY - INTERCHANGE SEC.

BELTLINE HIGHWAY

LANE COUNTY
FEBRUARY 2019


Length Of Project : 0.6 Miles

INDEX OF SHEETS	
SHEET NO.	DESCRIPTION
A01	Title Sheet
A02	Title Sheet
A03	Title Sheet
A04	Plan Sheet Layout



BEGINNING OF PROJECT
STA. "NW" 100+00
(OR 569 MP 10.04)


BEGINNING OF PROJECT
STA. "DH" 416+00



BEGINNING OF PROJECT
STA. "EN" 200+00
(OR 569 MP 9.73)

END OF PROJECT
STA. "DH" 447+00

END OF PROJECT
STA. "NW" 126+21.52
BEGINNING OF PROJECT
STA. "NE" 10+75.00



T. 17 S, R. 03 W, W.M.
T. 17 S, R. 04 W, W.M.

ATTENTION:
Oregon Law Requires You To Follow Rules Adopted By The Oregon Utility Notification Center. Those Rules Are Set Forth In OAR 952-001-0010 Through OAR 952-001-0090. You May Obtain Copies Of The Rules By Calling The Center. (Note: The Telephone Number For The Oregon Utility Center Is (503) 232-1987.)

LET'S ALL
WORK TOGETHER
TO MAKE THIS
JOB SAFE

OREGON TRANSPORTATION COMMISSION

CHAIR
Tommy Boney

COMMISSIONER
Bob Van Brocklin

COMMISSIONER
Alando Simpson

COMMISSIONER
Marfin Callery

COMMISSIONER
Julie Brown

DIRECTOR OF TRANSPORTATION
Matthew L. Garrett

These plans were developed using ODOT design standards. Exceptions to these standards, if any, have been submitted and approved by the ODOT Chief Engineer or their delegated authority.


Approving Authority: _____
Signature & date


Print name and title _____

Concurrence By ODOT Chief Engineer _____


OR569: BELTLINE @ DELTA HIGHWAY - INTERCHANGE SEC.
BELTLINE HIGHWAY
LANE COUNTY

FEDERAL HIGHWAY ADMINISTRATION	PROJECT NUMBER	SHEET NO.
OREGON DIVISION	SO-S069(019)	1A





2020 SW 4TH AVE. - 3RD FLOOR
PORTLAND, OR 97201-4953
TEL. 503.235.5000




**OR569: BELTLINE @
DELTA HIGHWAY - INTERCHANGE SEC.**

BELTLINE HIGHWAY
LANE COUNTY


Designer: B. Niamcoogo
Drafter: M. Wainscott

Reviewer: S. Litchfield
Checker: J. Bland



PLAN SHEET LAYOUT

SHEET NO. A04





2020 SW 4TH AVE. - 3RD FLOOR
PORTLAND, OR 97201-4953
TEL. 503.235.5000

OR569: BELTLINE @ DELTA HIGHWAY - INTERCHANGE SEC.

BELTLINE HIGHWAY
LANE COUNTY

Designer: D. Alves
Reviewer: S. Litchfield
Drafter: M. Wainwright
Checker: R. Attanasio


SHEET NO.
C01C



- ① Sta. "NW" 104+43.28, 21.19' Lt.
Inst. 12" DI storm sew. pipe - 66' (NE)
5' depth
Inst. 12" DI storm sew. pipe - 63' (SW)
5' depth
Const. type "G-2" Conc. inlet with sump
Grate Elev. = 393.71
I.E. (IN) = 390.66 (NE)
I.E. (IN) = 390.66 (SW)
I.E. (OUT) = 390.66 (NW)
- ② Sta "NW" 104+07.36, 66.96' Lt.
Inst. 12" storm sew. pipe with sloped
end section - 55' (S) 5' depth
I.E. (OUT) = 390.50 (E)
- ③ Sta. "NE" 11+00.00, 14.74' Lt.
Const. type "G-2" Conc. inlet with sump
Grate Elev. = 397.75
I.E. (OUT) = 394.30 (SW)
- ④ Sta. "NE" 11+20.28, 15.76' Lt.
Inst. 12" storm sew. pipe - 20'
5' depth
Const. type "G-2" conc. inlet with sump
Grate Elev. = 397.83
I.E. (IN) = 394.06 (NE)
I.E. (OUT) = 393.86 (SW)
- ⑤ Sta. "NE" 13+00.00, 18.73' Lt.
Inst. 18" storm sew. pipe - 179' (NE)
10' depth
Inst. 18" storm sew. pipe - 196' (SW)
10' depth
Const. storm manhole 48" dia. with inlet grate
Rim Elev. = 401.97
I.E. (IN) = 391.80 (E)
I.E. (IN) = 391.49 (NW)
I.E. (OUT) = 391.29 (N)
- ⑥ Sta. "NE" 12+89.32, 90.45' Rt.
Inst. 18" storm sew. pipe with sloped
end section - 112' (SE) 10' depth
I.E. (OUT) = 390.95
- ⑦ Sta. "NE" 15+00.05, 24.74' Lt.
Inst. 18" storm sew. pipe - 117' (SW)
10' depth
Const. storm manhole 48" dia.
Rim Elev. = 404.13
I.E. (IN) = 392.55 (SW)
I.E. (OUT) = 392.35 (NE)
- ⑧ Sta. "NE" 16+25.30, 24.50' Lt.
Inst. 12" storm sew. pipe - 55' (NW)
10' depth
Inst. 18" storm sew. pipe - 208' (SW)
10' depth
Const. storm manhole 48" dia. with inlet grate
Grate Elev. = 402.18
I.E. (IN) = 397.00 (NW)
I.E. (IN) = 393.26 (SW)
I.E. (OUT) = 393.06 (NE)
- ⑨ Sta. "NW" 118+77.16, 10.73' Lt.
Inst. 12" storm sew. pipe - 38' (W)
5' depth
Const. storm manhole 48" dia. with inlet grate
Grate Elev. = 404.99
I.E. (IN) = 398.83 (W)
I.E. (OUT) = 398.60 (SE)

- ⑩ Sta. "DH" 426+36.97, 58.65' Lt.
Const. type "G-2" conc. inlet with sump
Grate Elev. = 402.95
I.E. (OUT) = 399.00 (SE)
- ⑪ Sta. "DH" 428+24.45, 46.29' Lt.
Const. type "G-2" conc. inlet with sump
Inst. 12" storm sew. pipe - 33' (NE)
5' depth
Grate Elev. = 401.21
I.E. (IN) = 397.00 (NE)
I.E. (OUT) = 397.00 (SE)
- ⑫ Sta. "DH" 423+99.09, 55.07' Lt.
Inst. 12" storm sew. pipe with sloped
end section - 21' (NW)
5' depth
I.E. (OUT) = 410.54
Riprap Outlet (Cl. 50)(18" depth)
- ⑬ Sta. "DH" 424+00.00, 32.73' Lt.
Const. type "G-2" conc. inlet with sump
Grate Elev. = 415.09
I.E. (OUT) = 411.00 (SE)
- ⑭ Sta. "DH" 421+69.36, 32.60' Rt.
Const. type "G-2" conc. inlet with sump
Grate Elev. = 419.09
I.E. (OUT) = 414.00 (S)
- ⑮ Sta. "DH" 423+98.37, 24.73' Rt.
Inst. 18" storm pipe - 229' (N)
5' depth
Const. storm manhole 48" dia. with inlet grate
Grate Elev. = 414.86
I.E. (IN) = 409.90 (N)
I.E. (OUT) = 407.00 (S)
- ⑯ Sta. "DH" 425+23.08, 32.19' Rt.
Inst. 18" storm pipe - 125' (NE)
10' depth
Inst. 18" storm pipe - 179' (SW)
20' depth
Const. storm manhole 48" dia. with inlet grate
Rim Elev. = 411.01
I.E. (IN) = 398.00 (N)
I.E. (IN) = 394.48 (SW)
I.E. (OUT) = 394.28 (NW)
- ⑰ Sta. "DH" 427+01.41, 43.69' Rt.
Inst. 12" storm sew. pipe - 275' (SW)
10' depth
Const. storm manhole 48" dia. with inlet grate
Grate Elev. = 404.73
I.E. (IN) = 395.47 (SW)
I.E. (OUT) = 395.27 (NE)
- ⑱ Sta. "EN" 218+24.54, 18.73' Rt.
Inst. 18" storm sew. pipe - 201' (SE)
20' depth
Const. storm manhole 48" dia. with inlet grate
Rim Elev. = 405.82
I.E. (IN) = 393.59 (SE)
I.E. (OUT) = 393.39 (NW)
- ⑲ Sta. "NW" 105+20.00, 19.86' Rt.
Const. type "G-2" conc. inlet with sump
Grate Elev. = 392.70
I.E. (OUT) = 390.98 (W)
- ⑳ Extend 18" culvert Rt. 6'

- ㉑ Sta. "NW" 103+74.74, 31.35' Lt.
Replace extg. 18" PVC pipe with
new 12" DI storm sew. pipe - 121' (SW)
5' depth
Const. type "G-2" conc. inlet with sump
Grate elevation = 393.80
I.E. (IN) = 391.01 (S)
I.E. (OUT) = 391.01 (E)
- ㉒ Sta. "BL" 103+83.14, 80.42' Rt.
Protect extg. catch basin
I.E. (IN) = 393.89 (S)
- ㉓ Sta. "NE" 18+41.58, 18.73' Lt.
Const. type "G-2" conc. inlet with sump
Inst. 12" storm sew. pipe - 185' (SW)
5' depth
Inst. 12" storm sew. pipe - 63' (NW)
5' depth
Grate Elev. = 398.82
I.E. (IN) = 394.30 (SW)
I.E. (IN) = 394.30 (NW)
I.E. (OUT) = 394.10 (NE)
- ㉔ Sta. "DH" 427+93.64, 52.50' Lt.
Const. type "G-2" Conc. inlet with sump
Grate Elev. = 400.66
I.E. (OUT) = 397.15 (SW)
- ㉕ Extend 18" culvert Lt. 11'



EXPIRES: 12/31/2019


2020 SW 4TH AVE. - 3RD FLOOR
PORTLAND, OR 97201-4953
TEL. 503.235.5000

OR569: BELTLINE @ DELTA HIGHWAY - INTERCHANGE SEC.
BELTLINE HIGHWAY
LANE COUNTY

Designer: D. Alves
Reviewer: S. Litchfield
Drafter: M. Wainscott
Checker: R. Attanasio

DRAINAGE AND UTILITIES NOTES

SHEET NO. C01D



"NW" 100+00 "NW" 105+00 "NW" 110+00 52V-27

REGISTERED PROFESSIONAL ENGINEER
 RICHARD E. ATTANASIO
 LICENSE NO. 15058PE
 STATE OF OREGON
 EXPIRES: 12/31/2019

REGISTERED PROFESSIONAL ENGINEER
 J. BLAND
 LICENSE NO. 17643
 STATE OF OREGON
 EXPIRES: 12/31/2019

ROADWAY

2020 SW 4TH AVE. - 3RD FLOOR
 PORTLAND, OR 97201-4953
 TEL. 503.235.5000

OR569: BELTLINE @ DELTA HIGHWAY - INTERCHANGE SEC.

BELTLINE HIGHWAY
 LANE COUNTY


Designer: B. Niamogo
 Drafter: M. Wainwright
 Reviewer: S. Litchfield
 Checker: J. Bland

PROFILE

SHEET NO. **CO1E**

Horizontal Scale in Feet: 0, 50, 100, 150

Vertical Scale in Feet: 0, 5, 10, 15




"NE"10+00 "NE"15+00 "NE"20+00 "SE"500+00 "SE"504+C

ch2m
 2020 SW 4TH AVE. - 3RD FLOOR
 PORTLAND, OR 97201-4953
 TEL. 503.235.5000

REGISTERED PROFESSIONAL ENGINEER
 ROADWAY
 RICHARD E. ATTANASIO
 15058PE
 17643
 1/17/1995
 FOR REVIEW ONLY

REGISTERED PROFESSIONAL ENGINEER
 DRAINAGE
 RICHARD E. ATTANASIO
 15058PE
 17643
 1/17/1995
 FOR REVIEW ONLY



OR569: BELTLINE @ DELTA HIGHWAY - INTERCHANGE SEC.
 BELTLINE HIGHWAY
 LANE COUNTY



Designer: B. Niamcoego
 Drafter: M. Wainscott
 Reviewer: S. Litchfield
 Checker: J. Bland

PROFILE
 SHEET NO. C01G

EXPIRES: 12/31/2019

EXPIRES: 12/31/2019

BIOSWALE 2 PLAN
DFI #: D01207



- 1 Inst. riprap basin - 2
(For details, see sht. HA10)
- 2 Const. ditch "V" bottom, 1:4 sideslopes
(For details, see sht. HA10)
- 3 Inst. 18' double swing locked gate,
(See drg. No. RD820)
- 4 Inst. bollard - non-removable - 2
(see drg. no. RD130)
- 5 Const. gravel access road,
(For details, see sht. HA10)
- 6 Const. Bioswale 2,
(For details, see sht. HA10)
- 7 Match existing grade with AC pavement
- 8 Inst. flow spreader - 2
(For details, see sht. HA10)
- 9 Inst. Stormwater Facility Field Marker - 2
Type S1, (see drg. no. RD399)
- 10 Inst. Stormwater Facility Field Marker - 2
Type S2, (see drg. no. RD399)

2020 SW 4TH AVE. - 3RD FLOOR
PORTLAND, OR 97201-4953
TEL. 503.235.5000


OR569: BELTLINE @ DELTA HIGHWAY - INTERCHANGE SEC.

BELTLINE HIGHWAY
LANE COUNTY

Designer: M. Little
Checker: R. Attanasio



WATER QUALITY

SHEET NO.
HA03



- ① Finish grade
- ② Existing grade
- ③ Gravel access road

PROFILE "SW2"



ch2m
 2020 SW 4TH AVE. - 3RD FLOOR
 PORTLAND, OR 97201-4953
 TEL. 503.235.5000



OR569: BELTLINE @ DELTA HIGHWAY - INTERCHANGE SEC.
 BELTLINE HIGHWAY
 LANE COUNTY

Designer: M. Little
 Drafter: J. Pfeifer



Reviewer: S. Litchfield
 Checker: R. Attanasio

WATER QUALITY




SHEET NO.
HA04



FILTER STRIP
NTS



FLOW SPREADER
NTS



2020 SW 4TH AVE. - 3RD FLOOR
 PORTLAND, OR 97201-4953
 TEL. 503.235.5000

OR569: BELTLINE @ DELTA HIGHWAY - INTERCHANGE SEC.
 BELTLINE HIGHWAY
 LANE COUNTY

Designer: M. Little
 Reviewer: S. Litchfield
 Drafter: J. Pfeiffer
 Checker: R. Attanasio

SHEET NO.
HA10

REGISTERED PROFESSIONAL ENGINEER
 15058PE
 RICHARD E. ATTANASIO
 EXPIRES: 12/31/2019